

6d

**RIDGEFIELD BRICK AND TILE
RIDGEFIELD, WASHINGTON**

**FINAL OPERATION AND MAINTENANCE
INSPECTION REPORT**

WA 6906
~~WA 8411~~

Prepared For

**U.S. ENVIRONMENTAL PROTECTION AGENCY
Office of Waste Program Enforcement
Washington D.C. 20460**

EPA Identification No.	:	WAD 00903 6906
Work Assignment No.	:	WAD-009422411
EPA Region	:	12R10047
Contract No.	:	10
Date prepared	:	68-W9-0009
Prepared by	:	August 27, 1992
	:	PRC Environmental
	:	Management, Inc.
	:	Ben Farrell
Project Manager	:	Gary A. Bruno
Telephone No.	:	(206) 624-2692
EPA Primary Contact	:	Marcia Bailey
Telephone No.	:	(206) 553-0684



TABLE OF CONTENTS

<u>Section</u>	<u>Page</u>
EXECUTIVE SUMMARY	iv
1.0 INTRODUCTION	1
2.0 SETTING AND SITE HISTORY	1
3.0 SITE GEOLOGY AND HYDROGEOLOGY	3
4.0 GROUNDWATER MONITORING SYSTEM	3
5.0 SITE INSPECTION	5
5.1 WELL MAINTENANCE AND ABOVEGROUND WELL CONSTRUCTION	5
5.2 WATER-LEVEL MEASUREMENTS	5
5.3 WELL PURGING AND ENVIRONMENTAL PARAMETERS	6
5.4 SAMPLE COLLECTION	7
6.0 FACILITY ANALYTICAL DATA	9
7.0 EPA ANALYTICAL DATA	9
8.0 HISTORICAL ANALYTICAL DATA	12
9.0 GROUNDWATER SITE CHARACTERIZATION	13
10.0 SUMMARY	14
11.0 RECOMMENDATIONS	16
12.0 BIBLIOGRAPHY	18
<u>Appendices</u>	
A PHOTOGRAPHIC LOG	
B POTENTIOMETRIC SURFACE MAPS	
C PRC FIELD NOTES	
D OPERATION AND MAINTENANCE FIELD INSPECTION CHECKLIST	
E RBT ANALYTICAL DATA SUMMARY	
F EPA ANALYTICAL DATA SUMMARY	
G WELL CONSTRUCTION DIAGRAMS	

TABLE

Page

I	DETECTED COMPOUNDS	10
---	--------------------------	----

FIGURE

Page

I	RBT WELL LOCATION MAP	4
---	-----------------------------	---

EXECUTIVE SUMMARY

PRC Environmental Management, Inc. (PRC) assessed all of the monitoring wells and the toe drain at the Ridgefield Brick and Tile (RBT) site and determined that the aboveground construction of the monitoring wells was adequate for the collection of representative groundwater samples. However, the sampling procedures used by the facility, the maintenance of the monitoring wells, and the field sampling plan were generally inadequate to ensure the collection of representative groundwater samples.

PRC notes the following deficiencies regarding groundwater and toe drain sampling procedures: absence of gloves during sample collection, inaccurate water-level measurements, inadequate decontamination procedures, lack of environmental parameter collection during purging, and inadequate containment of purge water.

The maintenance of the groundwater monitoring system is inadequate for the collection of representative samples. Turbidity of the groundwater samples was relatively high (25-340 NTU) indicating potentially inadequate well development. This high turbidity may affect analytical results.

The sampling and analysis plan used by the facility is inadequate in that it provides little or no details regarding sampling schedules, sample collection procedures, decontamination methods, analytical methods and quality assurance/quality control procedures. Data reported by the facility was inadequate in that sample numbers were not cross referenced to existing well locations.

Facility analytical results for this round of split groundwater sampling show no phenols, polynuclear aromatic hydrocarbons (PAHs), arsenic, or chromium present in concentrations above the method reporting limit of the facility laboratory. Results from U.S. Environmental Protection Agency (EPA) split groundwater samples collected during this round of sampling show the presence of a number of volatile organic compounds, phenols, and PAHs in concentrations below the method reporting limit of the facility laboratory, indicating the possibility for groundwater contamination to exist and not be detected by the facility's analytical program. Arsenic and chromium were detected at maximum concentrations of 2.4 µg/L and 15.6 µg/L, respectively, in unfiltered EPA groundwater and leachate split samples. It is possible that the detected arsenic, chromium, and PAHs are related to the particulate fraction suspended in the groundwater and leachate samples.

Hydrogeologic site characterization remains incomplete. Because observed water-level measurements were inaccurate and the monitoring wells are dry for much of the year,

groundwater flow directions have not been adequately demonstrated for the perched groundwater zone. The requirement for one upgradient and three downgradient wells stipulated in 40 CFR 265.91 (a)(1) and 40 CFR 265.91 (a)(2) is not met because groundwater flow directions have not been adequately demonstrated. The perched groundwater zone is only seasonally saturated and can be used for detection of releases from the RBT landfill only when there is sufficient water for the collection of representative groundwater samples. Because the monitoring wells seasonally contain little or no water, monitoring the existing wells on a quarterly basis will not adequately detect potential releases from the landfill. One alternative would be to install a monitoring well system in the uppermost aquifer (the regional Troutdale aquifer) as required by 40 CFR 265.90 (a).

Another alternative would be to sample the landfill toedrain and underdrain system sumps in addition to the existing monitoring well system. An underdrain system located beneath the liner of the landfill has recently been described. EPA has expressed concern that leachate from the landfill may not be transported far enough horizontally to reach the monitoring wells. The underdrain sump could be sampled to provide analytical data for perched groundwater beneath the landfill. In addition, data collected during this O & M inspection suggest that groundwater collected from monitoring wells screened in the perched groundwater zone is in contact with the contents of landfill; several of the wells show low levels of contaminants.

During dry periods when there not enough water in the perched groundwater zone to monitor, there is also less water passing through the landfill. Consequently, there is less of a chance for a significant release. During the wet season when the maximum quantity of water is passing through the landfill, the wells, toe drain sump, and underdrain sump could be sampled in order to detect significant releases from the RBT landfill. A rigorous monitoring program should be developed to determine when sufficient water is present in the wells, toe drain, or underdrain system for the collection of samples. Under this monitoring program, it is very important to obtain water quality samples for the initial pulse of water passing through the waste at the beginning of the wet season. This water will likely have the highest concentration of contaminants. One sampling round should be scheduled to coincide with this initial fall flush. Two more sampling rounds should be performed during the wet season when there is sufficient water for sampling (November through March). A fourth round should be attempted after a significant storm event during the dryer part of the year (May through August). If significant concentrations of contaminants are detected in the monitoring wells or the underdrain sump during these rounds of sampling, the facility should install monitoring wells screened in the regional aquifer (Troutdale Formation).

1.0 INTRODUCTION

PRC Environmental Management, Inc. (PRC) received work assignment no. 12R10047 from the U.S. Environmental Protection Agency (EPA) to conduct an operation and maintenance (O&M) inspection at the Ridgefield Brick and Tile (RBT) landfill in Ridgefield, Washington. At the request of EPA, PRC performed the O&M inspection to evaluate how facility personnel operate and maintain the groundwater monitoring system in terms of pertinent Resource Conservation and Recovery Act (RCRA) regulations and permit requirements. This report describes the O&M inspection conducted on March 27 - March 28, 1991 at the RBT site.

The specific objectives of the RBT O&M inspection were as follows:

- Evaluate the compliance of the groundwater monitoring system with the consent agreement and final order (EPA 1986a), RCRA interim status groundwater monitoring regulations (40 CFR 265 Subpart F), and protocols specified by EPA (1986b)
- Determine whether sampling devices are in working order and are properly maintained
- Evaluate the facility sampling and analysis plan
- Determine whether individual monitoring wells yield representative groundwater data
- Evaluate groundwater contamination from analytical results of split groundwater samples received by PRC
- Evaluate the analytical program of the facility through the comparison of facility and split sample analytical results

PRC personnel present on-site were geologists Ben Farrell and Gary Bruno. Technical points were discussed with Bryant Adams of Pacific Wood Treating Corporation (PWT) and Mike Buren of David J. Newton Associates, a consultant to PWT.

2.0 SETTING AND SITE HISTORY

The RBT site is an inactive landfill located in a rural area at 3510 N.W. 289th street in Ridgefield, Washington. PWT owns the 5.5-acre landfill and also owns and operates an active wood-treating facility in nearby Ridgefield. The PWT wood-treating facility uses pentachlorophenol, creosote, and a chrome-copper-arsenic solution as preservatives (Tetra Tech 1989). In 1979, PWT began to use the RBT landfill for the disposal of log-deck waste, yard

cleanup waste, and boiler ash. Between 1979 and January 1983, PWT disposed of approximately 7,600 yd³ of waste (EPA 1986a) in the RBT landfill. Of this amount, 2,500 yd³ consisted of boiler ash (Hazard Management Specialists 1987 in Tetra Tech 1989). An estimated 5 yd³ (5,000 lb) of the boiler ash result from wastewater sludge incineration (Tetra Tech 1989).

Wastewater sludge generated from the wood-treating activities is designated as a K001 (creosote/pentachlorophenol wastewater treatment sludge) and D004 (arsenic) hazardous waste. As specified in 40 CFR 261.3 (b)(2) and 40 CFR 261.3 (c)(2)(i), all ash derived from the incineration of the sludge and all solid waste (boiler ash) mixed with a K001-listed waste will retain the K001 hazardous waste listing.

During an EPA inspection of the PWT wood treating facility in Ridgefield, Washington, it was discovered that RCRA-listed and regulated K001/D004 waste was being disposed of in the unregulated RBT landfill (Tetra Tech 1989). PWT subsequently submitted a RCRA Part A permit application for the RBT landfill on May 25, 1983 and gained interim status. A closure plan for the RBT landfill was submitted to the Washington Department of Ecology (Ecology), and closure activities were conducted during September 1983 under Ecology supervision (Tetra Tech 1989). A wedge-shaped landfill cell equipped with a drain system was constructed as part of this closure effort. All wastes were transferred into the cell in compacted 18-inch lifts and covered with a compacted clay cap (Tetra Tech 1989).

As a result of the deficiencies in the original closure plan and closure activities, EPA issued a consent agreement and final order to PWT in November 1986. This order stated that PWT would submit a closure plan within 3 months pursuant to 40 CFR 265 subpart G, addressing the installation of a groundwater monitoring system in compliance with 40 CFR 265 subpart F capable of providing hydrogeological information to satisfy the requirements of 40 CFR 270.14 (c). As required by the order, PWT submitted a revised closure plan in February 1987. The plan was determined deficient by EPA because it did not address the hydrogeologic characterization requirements of 40 CFR 270.14 (c), the requirements of 40 CFR 265.90 (a) regarding groundwater monitoring of the uppermost aquifer, and the requirements of 40 CFR 265.92 and 40 CFR 265.93 pertaining to the selection of appropriate analytical parameters for groundwater monitoring.

Clean closure is being considered by the facility in an effort to avoid postclosure requirements. Clean closure may be possible for RBT through a removal action (EPA 1990b). Alternately, clean closure may be possible through a detailed demonstration that all components of the landfill are not contaminated above health-based criteria and do not exhibit any of the characteristics of hazardous waste (EPA 1990b). The facility submitted a delisting petition in an

effort to delist the contents of the landfill in 1987. This petition had not been approved and a revised closure plan had not been received at the time of the inspection. A monitoring well system was installed in August 1988.

3.0 SITE GEOLOGY AND HYDROGEOLOGY

There are two potential aquifers of concern underlying the RBT site. The upper perched water zone occurs in a series of Quaternary sands, silts, and clays. Lithologic logs from borings at the RBT site show that the Quaternary alluvial deposits occur as three distinct lithologic units. From top to bottom these include: a 10- to 25-foot thick clayey silt unit, a silty micaceous sand unit, and a basal clean sand unit. The silty micaceous sand and clean sand units appear to pinch out to the west of the landfill and thicken to the east, reaching a maximum combined thickness of approximately 20 feet. The quaternary alluvial deposits are underlain by weathered gravel deposits of the Troutdale Formation. Seasonal perched water exists in the sand and silt units that rest upon the Troutdale Formation.

The direction of groundwater flow within the perched zone is reported to be toward the northwest at the RBT site (DNA 1990). At the southern portion of the landfill, the direction of groundwater flow may be to the southeast (DNA 1990). See Appendix B for potentiometric surface maps of the RBT site. As discussed in Section 5.2, poor procedures for water-level measurement observed during this inspection and the frequent historical absence of water in the wells cast doubt on the validity of the potentiometric surface maps.

The deeper regional aquifer occurs in silts and sands of the Tertiary Troutdale Formation. Depth-to-water in the Troutdale Formation is approximately 180 feet below ground surface (bgs). The direction of groundwater flow within the Troutdale aquifer is generally toward the northwest in the general vicinity of the RBT site (Tetra Tech 1989).

4.0 GROUNDWATER MONITORING SYSTEM

The RBT groundwater monitoring system consists of seven wells (B-1 through B-7). Monitoring well locations are shown in Figure 1. Monitoring well B-5 is the facility designated upgradient well, while all of the other wells are either cross-gradient or downgradient of the landfill. As discussed in Section 5.2, the accuracy of these designations is questionable. Monitoring wells B-2, B-3, and B-4 are screened in clayey silts and the Troutdale gravels beyond the westward limit of the sand facies (DNA 1988). All of the other wells are screened across the




Figure 1
RBT Well Location Map

contact between the sand layers and the Troutdale Formation gravels (DNA 1988). The monitoring wells often become dry in the spring, summer, and fall.

5.0 SITE INSPECTION

On March 27-28, 1991, PRC conducted the O&M inspection at RBT. On March 27, 1991, the weather was generally sunny and temperatures ranged between 55 and 65°F. On March 28, 1991, the weather was rainy and temperatures ranged between 45 and 55°F. PRC personnel observed water-level measurements at all of the monitoring wells. Split groundwater samples were received by PRC personnel from monitoring wells B-4, B-5, and B-6. Water accumulating in the stand pipe to the toe drain of the landfill was also split-sampled. A photographic log of the site visit is presented in Appendix A. Potentiometric surface maps, PRC field notes, the O&M inspection checklist, RBT analytical data, EPA analytical data, and well construction diagrams are presented in Appendices B through G, respectively.

5.1 WELL MAINTENANCE AND ABOVEGROUND WELL CONSTRUCTION

The aboveground portion of the monitoring wells appeared to be adequately maintained. The wells were constructed with lockable protective outer casings that were securely locked. The protective outer casings were set into small circular concrete bases that appeared to fit tightly against protective outer casings. Each well was equipped with an inner well cap. None of the inspected wells were labelled. The outer casings of all the monitoring wells were quite rusted, and the monitoring wells did not have protective posts to shield the wells from collision.

5.2 WATER-LEVEL MEASUREMENTS

Water-levels were measured both before and after purging to determine if there was sufficient groundwater for sample collection. Depth-to-water was measured using an electronic probe and a separate stainless steel measuring tape. Measurements were taken from the edge of the outer protective casing. The stainless steel tape was not decontaminated prior to use, and the facility representative stated that it had also been used at the PWT wood-treating plant. At the request of PRC, the well probe was decontaminated by rinsing the probe tip and attached tape with deionized water. After the water-level was measured at monitoring well B-6, a large number of unidentified larvae were found on the well probe.

The well probe had been cut and respliced so that a given measured distance had to be corrected to account for the shortening of the well probe. The stainless steel measuring tape was

commonly used in the correction process. Based on observed measuring practices, the water-level measurements were not accurate to within .01 foot, as recommended by EPA (1986b).

Examination of the water-level data used for the construction of potentiometric surface maps raises further questions concerning the quality of the data. Water-level measurements recorded large differences over short time periods. For example, between January 12, 1990 and January 15, 1990 (the two dates used to create the potentiometric maps shown in Appendix B), the water-level in monitoring well B-1 reportedly dropped 26.4 feet (DNA 1990). Fluctuations of this magnitude also have been reported for monitoring well B-4 over time spans of approximately 1 week (DNA 1990). It is likely that errors were made by the facility during water-level measurements, because such rapid water-level fluctuations cannot be explained hydrogeologically.

An examination of the potentiometric surface map for January 12, 1990 (Appendix B) reveals that water-levels for monitoring wells B-2, B-3, and B-7 were below the top of the Troutdale Formation. It is unclear whether the measured water-levels in these wells represent the potentiometric surface for the perched zone, since the water-levels occur in screened intervals situated below the top of Troutdale Formation.

5.3 WELL PURGING AND ENVIRONMENTAL PARAMETERS

Well purging and sampling was accomplished using a top-emptying teflon bailer. EPA (1986b) states that a bottom-emptying bailer is more appropriate for the collection of volatile organic compounds than a top-emptying bailer. The bailer was lowered slowly into the wells using a synthetic measuring tape. Due to low water-levels and slow recharge rate in monitoring wells B-4 and B-5, these two wells were purged to dryness on the day prior to sampling to allow sufficient recovery time. Monitoring wells B-1, B-2, and B-7 also did not contain enough water for purging and groundwater sampling during the site inspection.

PRC personnel observed groundwater purging at monitoring well B-6 on March 27, 1991. At monitoring well B-6, three casing volumes were purged from the well. Purge water was poured directly onto the ground surface. No environmental parameters such as conductivity, pH, temperature, or turbidity were collected during well purging. Groundwater from the monitoring wells was quite turbid, resulting in sample collection problems described in Section 5.4. The groundwater turbidity increased during purging. Leachate purged from the landfill toe drain was significantly less turbid than the groundwater. The leachate sample collected from the standpipe inlet was nearly clear.

5.4 SAMPLE COLLECTION

After well purging, groundwater samples were collected by the facility contractor. Split groundwater and leachate samples received by PRC were analyzed for the following parameters by the EPA Manchester Laboratory:

- Volatile organic compounds (modified SW-846 method 8260 [EPA 1986c])
- Polynuclear aromatic hydrocarbons (PAH) and chlorophenols (special analytical services method gas chromatograph/mass spectrometer, selected ion monitoring mode)
- Total arsenic and chromium (EPA methods 206.2 and 218.2, respectively [EPA 1983])
- Total arsenic and chromium (field-filtered using same analytical methods specified above)

The PRC Quality Assurance Project Plan (QAPjP) (PRC 1991) specified monitoring wells B-3, B-4, B-5, and B-6 for groundwater sampling. Monitoring well B-3 was not sampled due to lack of water in the well. The PRC QAPjP also specified that triple sample volumes would be collected for matrix spike/matrix spike duplicate (MS/MSD) analysis at monitoring well B-5. Because of low water-levels in monitoring well B-5, the MS/MSD sample volumes were collected at monitoring well B-4. Due to the relatively low water-level in monitoring well B-4, double sample volumes were collected in lieu of triple sample volumes. This reduction of sample volume did not affect sample results. No samples were collected for arsenic and chromium analysis at monitoring well B-5 due to the low water-level.

PWT personnel submitted groundwater and leachate samples for the following analyses:

- PAHs (SW-846 methods 3510/8100 [EPA 1986c])
- Chlorinated phenolic compounds (SW-846 methods 3510/modified 8150 [EPA 1986c])
- Total organic carbon (EPA method 415.1 [EPA 1983])
- Total arsenic and chromium (filtered) (SW-846 methods 7060 and 6010, respectively [EPA 1986c])
- Chloride, fluoride, nitrate, sulfate (EPA method 300 [EPA 1984])
- Turbidity (EPA method 180.1 [EPA 1983])
- pH and conductivity (EPA methods 150.1 and 120.1, respectively [EPA 1983])

The facility did not collect groundwater or leachate samples for volatile organic analyses.

Samples were generally collected in decreasing order of volatility. An exception to this trend occurred at monitoring well B-4, where metal samples were collected first. The rationale for collecting the metal sample first was that the groundwater appeared to become more turbid with successive bailing. Filtered metal samples proved to be very difficult to collect because the turbid groundwater samples clogged the filter apparatus. Facility personnel tried two different techniques for field-filtering the samples intended for metals analysis (see photographs 6 and 11). Because these methods were ineffective, the facility decided to not preserve the field-filtered metals samples and have the laboratory filter the samples. PRC personnel were able to filter all of their split samples to be analyzed for metals using Nalgene™ hand filters.

Monitoring well B-4 was sampled first because it contained the most water. Sampling next commenced at monitoring well B-5. However, due to insufficient groundwater in monitoring well B-5, the sampling crew decided to sample B-6 and then return to B-5 after the well had time to recharge. Monitoring well B-6 also had insufficient groundwater for the completion of split sampling. The sampling crew decided to finish sampling at B-5 and then return to B-6. After the completion of groundwater sampling at B-5, the sampling crew took water-level measurements at B-6. Because there was still insufficient water in this well, the sampling crew decided to return the next day (March 27, 1991) to complete groundwater sampling at this well. Monitoring well B-3, which is one of the wells specified for sampling in the PRC QAPjP (PRC 1991), was not sampled because sufficient sample volume could not be obtained in a reasonable time period.

After sampling, the PWT sample containers were placed in coolers with a small amount of ice. The facility groundwater split samples were hand-delivered to Columbia Analytical Services in Kelso, Washington on March 28, 1991.

Leachate split samples were collected from the vertical standpipe at the toe drain of the landfill on March 27, 1991. The 8-foot long, 3-foot diameter, vertical standpipe is set approximately 6 feet bgs. The standpipe provides access to the landfill drainage system, which drains to a large storage container located at the southern portion of the property. The bailer was rinsed with deionized water prior to purging. The first split sample, designated TD-1 by PRC, was collected with the same bailer used for groundwater sample collection from standing water that had collected in the toe drain. An EPA duplicate sample designated TD-10 was also collected from the standing water in the toe drain. After collection of the first sample, RBT

personnel purged the standpipe. RBT personnel then climbed into the standpipe with a ladder and collected a leachate split sample (TD-2) directly from the standpipe inlet.

6.0 FACILITY ANALYTICAL DATA

The facility analytical results for the split sampling event are not complete. According to the chain-of-custody sheet, a total of six samples was submitted for chemical analysis. The samples are numbered, but are not cross referenced to existing well locations. The collection of rinsate blanks and field (transfer) blanks by the facility sampling team was not observed by PRC personnel. Based on the facility chain-of-custody sheet, sample 28, which is one of the toe drain samples based on the date of collection, was not analyzed. Sample 25 was analyzed for organic parameters, but not for inorganic parameters. No rationale was provided by the facility for omitting these samples from analysis.

The facility analytical results show no PAHs, phenols, arsenic, or chromium above the method reporting limit of the facility laboratory. The turbidity values for all of the groundwater samples are high (25-340 NTU). The maximum recommended level for turbidity is 5 NTU measured on consecutive days (EPA 1990a). Concentrations of nitrate, chloride, fluoride, and sulfate are below state and federal primary and secondary groundwater quality criteria as established by the Washington Administrative Code (WAC 173-200-040) and EPA (1990a). It should be noted that the state and federal primary groundwater criteria specify the concentration of nitrate measured as nitrogen, while the facility measured nitrate as nitrate only. The pH values fall within the 6.5 to 8.5 range specified in state and federal secondary groundwater quality criteria.

7.0 EPA ANALYTICAL DATA

Complete results for the split groundwater and leachate samples received by PRC are shown in Appendix F. A summary of compounds detected in groundwater and leachate samples during the O&M inspection is shown in Table 1. In an effort to meet quality assurance/quality control objectives, PRC submitted a trip blank, an equipment rinsate blank for both the groundwater monitoring system and the toe drain system, an environmental duplicate for both the groundwater and toe drain systems, and a MS/MSD sample for chemical analysis. Data were validated by the EPA Manchester Laboratory using the guidelines established by EPA (1988a,b).

Table 1

Detected Compounds (µg/L)

<u>Inorganic Compounds</u>	<u>RB-B4-01</u>	<u>RB-B10-01</u> (duplicate of B4)	<u>RB-B5-01</u>	<u>RB-B6-01</u>	<u>RB-TD1-01</u>	<u>RB-TD2-01</u>	<u>RB-TD10-01</u> (duplicate of TD-1)
Total Arsenic	1.8J	2.4J	Not Sampled	1.9J	---	---	---
Filtered Arsenic	---	---	Not Sampled	1.9J	---	---	---
Total Chromium	15.6J	14.5	Not Sampled	1.7B	1.1B	1.9	1.4B
Filtered Chromium	1.3B	1.1B	Not Sampled	.7JB	.4JB	.9JB	.3JB
<u>Volatiles Organic Compounds</u>							
1,2-Dichloroethane	.8J	.2J	.5J	---	1.4	.4J	.4J
Chloromethane	---	.05J	.1J	---	---	---	---
Carbon disulfide	---	.2J	---	---	---	---	---
Chloroform	---	---	.1J	---	---	---	---
Chloroethane	---	---	---	---	1J	---	.1J
1,1-Dichloroethane	---	---	---	---	.2J	---	---
<u>Semivolatile Organic Compounds</u>							
Benzo(a)pyrene	.03J	.03J	.04J	.05J	---	---	---
Acenaphthene	.0006J	.0006J	.001J	.002J	.6J	.2J	.6J
Phenanthrene	.005J	.007J	.02J	.01J	.1J	.05J	.1J
Carbazole	.02J	---	---	---	.2J	.05J	.1J
Pentachlorophenol	.02J	.02J	.06J	.06J	.1J	.7J	.1J
4-Methylphenol	.0003J	---	---	---	.01J	.02J	.006J
Phenol	---	---	---	.9J	---	---	---
2-Methylphenol	---	---	---	---	.005J	.002J	.002J
2-Methylnapthalene	.002J	.003J	.005J	.004J	.02J	.004J	.01J
Naphthalene	---	---	---	---	.4J	.2J	.4J
1-Methylnapthalene	---	.003J	.005J	.005J	.1J	.05J	.1J
Pyrene	.02J	.01J	.02J	.02J	.08J	.02J	.09J
Dibenzofuran	.001J	---	---	.002J	.2J	.06J	.2J
Benzo(b)fluoranthene	.04J	.03J	.06J	.04J	---	---	---
Fluoranthene	.01J	.008J	.02J	.01J	.08J	.03J	.08J
Benzo(k)fluoranthene	.03J	.03J	.03J	.02J	---	---	---
Anthracene	---	---	---	---	.04J	.02J	.04J
Dibenzo(a,h)anthracene	---	.02J	---	---	---	---	---
Acenaphthylene	---	---	---	---	.02J	.007J	.01J
Fluorene	---	---	.002J	---	.2J	.1J	.2J
Benzo(g,h,i)perylene	---	---	---	.02J	---	---	---

--- Indicates that compound was not detected above instrument detection limit/method detection limit (U) or that the analyte was not detected at or above the reported result (UJ).

J Analyte was detected above the instrument/method detection limit but not quantified with expected limits of precision. Estimated concentration.

B Analyte also found in analytical method blank, indicates possible sample contamination.

Inorganic compound analysis reveals the presence of arsenic and chromium in both filtered and unfiltered groundwater and leachate samples from the RBT site. Maximum concentrations of arsenic ($2.4 \mu\text{g/L}$) and chromium ($15.6 \mu\text{g/L}$) were detected in a groundwater sample and duplicate groundwater sample from monitoring well B-4. The maximum value for arsenic is above the $.05\text{-}\mu\text{g/L}$ state of Washington primary groundwater standard (WAC 173-200-040) established for this carcinogenic compound, but below the $50\text{-}\mu\text{g/L}$ concentration established in the national interim primary drinking water standards (EPA 1990a). RBT chromium concentrations are below state and federal primary drinking water standards (WAC 173-200-040, EPA 1990a). Total arsenic and chromium concentrations are generally higher than the results for the field-filtered samples, indicating that the greatest concentrations of chromium and arsenic are in the suspended sediment fraction of the turbid groundwater samples. Chromium was detected in the method blanks. Therefore, all chromium results within 10 times the detection limit are qualified B (Appendix F). Due to a low water-level in the designated upgradient monitoring well B-5, no sample was collected at this well for arsenic and chromium analysis.

Results for PAH and phenol analysis also show the presence of several compounds. These compounds are all estimated at concentrations of less than or equal to $1 \mu\text{g/L}$ and are qualified J (Appendix F). The results from the toe drain samples show excellent correlation. The toe drain samples have exactly the same semivolatile organic compounds present. Pentachlorophenol was detected at a maximum estimated concentration of $1 \mu\text{g/L}$ in two samples collected from the toe drain. The following compounds were detected in all of the monitoring wells, but not in the toe drain leachate split samples: benzo(a)pyrene, benzo(b)fluoranthene, and benzo(k)fluoranthene. The concentrations of benzo(a)pyrene, benzo(b)fluoranthene, and benzo(k)fluoranthene all closely approach or exceed 10^{-6} cancer risk-based concentrations established by EPA (1991b).

Groundwater samples collected during this O&M inspection were quite turbid. The high degree of turbidity of groundwater samples collected in the facility monitoring wells is problematic in that high turbidity can adversely affect chemical analysis for any compound that has a tendency to adsorb onto sedimentary particles. Samples analyzed for arsenic and chromium were filtered to alleviate this problem. However, for some of the more insoluble PAH compounds, it is difficult to determine whether the detected contamination in the monitoring wells is related to the groundwater fraction or to the suspended sediment fraction.

Results for volatile organic compounds show very low concentrations of a few compounds, which are estimated at concentrations above the instrument detection limit and are designated J (Appendix F). Of these, 1,2-dichloroethane occurs in both toe-drain samples and in

all of the monitoring wells samples with the exception of monitoring well B-6. This compound was also found at the maximum concentration for any of the volatile organic compounds detected at the RBT site, 1.4 $\mu\text{g/L}$ for the TD-1 sample, but below the 5 $\mu\text{g/L}$ maximum contaminant level established for this compound (EPA 1990a). Chloromethane was detected in monitoring wells B-4 and B-5 in concentrations of less than 1 $\mu\text{g/L}$. All of the other detected compounds occurred in very low concentrations in a single monitoring well or toe drain sample.

Low levels of vinyl chloride, trichlorofluoromethane, 1,2-dichloroethane, toluene, carbazole, benzo(b)fluoranthene, fluoranthene, benzo(k)fluoranthene were detected in one or both equipment rinsate blanks. All of the above compounds were detected in concentrations of less than 1 $\mu\text{g/L}$ and were estimated J (Appendix F). Low levels of chloroform and dibromochloromethane were detected in the ambient condition blank, and chloroform was detected in the trip blank. The low levels of chloroform detected in the groundwater and leachate samples are probably the result of contamination during shipping or ambient contamination.

The presence of 1,2-dichloroethane, carbazole, benzo(b)fluoranthene, fluoranthene, and benzo(k)fluoranthene in the equipment rinsate blanks is problematic since these compounds also were detected in either groundwater or leachate samples. It is probable that the presence of these compounds in groundwater and leachate samples is related to poor equipment decontamination procedures since the compounds were not found in the laboratory blanks.

The detection of low levels of volatile organic compounds, PAHs, and phenols in the EPA split groundwater samples shows the potential for groundwater contamination to occur that would not be detected by the analytical program of the facility. The detection of arsenic and chromium at levels above the facility method reporting limit for nonfiltered EPA split groundwater samples shows the potential contamination associated with the sediment fraction suspended in the groundwater and the need for the facility to collect nonfiltered metals samples as well as filtered metals samples.

8.0 HISTORICAL ANALYTICAL DATA

Data collected by the facility between 1983 and 1986 show concentrations of naphthalene and pentachlorophenol at less than or equal to 10 $\mu\text{g/L}$ for on-site lysimeters, toe drain, and local wells (Hazard Management Specialists 1987). Arsenic and chromium were detected in concentrations below the federal primary drinking water standards, which are 50 and 100 $\mu\text{g/L}$, respectively. Data from a 1989 comprehensive groundwater monitoring evaluation (CME) show

PAH concentrations typically below 1 µg/L for leachate samples collected from the toe drain (Tetra Tech 1989). Naphthalene was detected at concentrations of 1.5 µg/L and 1.8 µg/L for toe-drain samples. A maximum pentachlorophenol concentration of .73 µg/L was reported from the toe drain during the CME sampling event. No groundwater samples were collected during the 1989 CME because of lack of water in the wells. The split samples collected by PRC confirm the presence of low concentrations of arsenic, chromium, volatile organic compounds, phenols, and PAHs in groundwater and leachate samples at the RBT site.

9.0 GROUNDWATER SITE CHARACTERIZATION

Groundwater characterization at the site remains incomplete. PWT's groundwater monitoring system is designed to monitor the shallow silt and sand aquifer, which is adequate to detect releases from the landfill only if there is enough water in the perched zone to monitor. The wells at RBT are dry for a significant portion of the year. For example, during September 1987 to May 1988, only one of the seven monitoring wells contained enough water for measurement during frequent measuring events (DNA 1990). During January to July 1990, at least one of the seven monitoring wells was dry during frequent water-level measurements (DNA 1990).

The seasonal dryness of the wells poses a problem from the well development standpoint. When wells are dry for substantial periods, fine-grained sediment may be flushed into the packing and through the well screen when water reenters during recharge events. Most of the wells are screened either in silt or across the silt/Troutdale gravel contact. The fine grain-size and lithologic variability within the screened interval can make well development difficult (EPA 1991a).

As discussed in Section 5.2, observed water-level measurements were not accurate to within .01 foot, as specified by EPA (1986b), and may be inaccurate by tens of feet. Also since most of the monitoring wells are dry for much of the year, groundwater flow directions cannot be adequately demonstrated for the perched groundwater zone. The requirement for one upgradient and three downgradient wells stipulated in 40 CFR 265.91(a)(1) and 40 CFR 265.91(a)(2) has not been met since groundwater flow directions have not been adequately delineated.

Because the monitoring wells seasonally contain little or no water, simply monitoring the existing wells on a quarterly basis will not adequately detect potential releases from the landfill.

One alternative would be to install a monitoring well system in the uppermost aquifer (the regional Troutdale aquifer) as required by 40 CFR 265.90 (a).

Another alternative would be to sample the landfill toedrain and underdrain system sumps in addition to the existing monitoring well system. An underdrain system located beneath the liner of the landfill has recently been described (DNA 1992). The underdrain consists of two perforated PVC pipes beneath the landfill liner that extend from the northeast and southeast corners of the landfill and join in the center of the west landfill boundary (DNA 1992). From the center of the west landfill boundary, a non-perforated PVC pipe carries water to a sump. The underdrain system was constructed to prevent liner damage caused by a seasonal rise in the perched zone (DNA 1992). EPA has expressed concern that leachate from the landfill may not be transported far enough horizontally to reach the monitoring wells (DNA 1992). The underdrain system could be sampled to provide analytical data for perched groundwater beneath the landfill. In addition, data collected during this O & M inspection suggest that groundwater collected from monitoring wells screened in the perched groundwater zone is in contact with the contents of landfill; several of the wells show low levels of contaminants.

During dry periods when there not enough water in the perched groundwater zone to monitor, there is also less water passing through the landfill. Consequently, there is less of a chance for a significant release. During the wet season when the maximum quantity of water is passing through the landfill, the wells, toe drain, and underdrain could be sampled in order to detect significant releases from the RBT landfill. A rigorous monitoring program should be developed to determine when sufficient water is present in the wells, toe drain, or underdrain system for the collection of samples. Under this monitoring program, it is very important to obtain water quality samples for the initial pulse of water passing through the waste at the beginning of the wet season. This water will likely have the highest concentration of contaminants. One sampling round should be scheduled to coincide with this initial fall flush. Two more sampling rounds should be performed during the wet season when there is sufficient water for sampling (November through March). A fourth round should be attempted after a significant storm event during the dryer part of the year (May through August). If significant concentrations of contaminants are detected in the monitoring wells or the underdrain sump during these rounds of sampling, the facility should install monitoring wells screened in the regional aquifer (Troutdale Formation).

10.0 SUMMARY

PRC assessed all of the monitoring wells at the RBT site and determined that the aboveground construction of the monitoring wells was adequate for the collection of

representative groundwater samples. However, the sampling procedures used by the facility, the maintenance of the monitoring wells, and the field sampling plan were generally inadequate to ensure the collection of representative groundwater samples.

The following deficiencies regarding groundwater and toe-drain sampling procedures were observed during the RBT O&M inspection:

- Sampling gloves were not worn by facility personnel during sample collection.
- Water-level measurements were not accurate to within .01 foot, as specified by EPA (1986b), because of measuring errors introduced through use of the spliced well probe and the metal tape.
- Metal tape often used to measure water-levels in the well was not decontaminated before or between use at monitoring wells. This tape was used in the Pacific Wood Treating shop prior to sampling.
- Equipment decontamination procedures were inadequate when practiced at all. Facility personnel were not equipped with necessary items for proper decontamination (Alconox wash, distilled water rinse, deionized water rinse). Only at the request of PRC was a deionized or distilled water rinse performed on sampling equipment.
- Conductivity, pH, and temperature were not measured during purging as specified by EPA (1986b).
- Purge water was discharged directly to the ground surface. This practice may spread potential contaminants present in the groundwater.

The maintenance of the groundwater monitoring system is inadequate for the collection of representative samples. Turbidity of the groundwater samples was relatively high (25-340 NTU). This high turbidity may affect analytical results. Unfortunately, the fine-grained lithology of the screened interval makes further well development impractical or impossible.

The sampling and analysis plan used by the facility at the time of the PRC O&M inspection is the same one viewed during the CME (Tetra Tech 1989). As noted in the CME report, the plan is inadequate in that it provides little or no detail regarding sampling schedules, sample collection procedures, decontamination methods, analytical methods, and quality assurance/quality control procedures. Data reported by the facility were inadequate in that sample numbers were not cross referenced to existing well locations.

Facility analytical results for this round of split groundwater sampling show no volatile organic compounds, phenols, PAHs, arsenic, or chromium present in concentrations above the method reporting limit of the facility laboratory. Results from EPA split groundwater samples

show the presence of a number of volatile organic compounds, phenols, and PAHs in concentrations below the method reporting limit of the facility laboratory, indicating the possibility that groundwater contamination exists and may not be detected by the facility's analytical program. Arsenic and chromium were detected at maximum concentrations of 2.4 µg/L and 15.6 µg/L, respectively, in unfiltered EPA groundwater and leachate split samples. It is possible that the PAH, arsenic, and chromium are related to the suspended sediment present in the turbid groundwater and leachate samples

Groundwater flow directions have not been adequately demonstrated for the perched groundwater zone. Also, the perched groundwater zone is only seasonally saturated and can be used for detection of releases from the RBT landfill only when there is sufficient water for the collection of representative groundwater samples. Because the monitoring wells seasonally contain little or no water, merely monitoring the existing wells on a quarterly basis will not adequately detect releases from the RBT landfill.

11.0 RECOMMENDATIONS

PRC recommends the following regarding observed sampling practices:

- Clean sampling gloves should be worn by facility personnel at each well during sampling.
- The spliced electronic water-level measurement device should not be used. Static water-levels for each well should be measured using appropriate equipment and should be accurate to within .01 foot as specified by EPA (1986b).
- The metal tape used for water-level measurements should not be used without proper decontamination.
- Proper decontamination procedures should be practiced by the facility in accordance with EPA (1986b).
- In accordance with EPA (1986b), temperature, pH, and specific conductance should be measured in the field during well purging. Groundwater sampling should not commence until these parameters have stabilized.
- The facility should consider containing purged groundwater until chemical testing is complete.

PRC recommends that the field sampling plan used by the facility be rewritten to provide adequate procedures and techniques as specified by EPA (1986b) for sample collection, preservation, and shipment; sample analysis; and chain-of-custody control. The facility should cross reference sample numbers with well locations. Because of the presence of arsenic and

chromium in concentrations above the method reporting limit, the facility should collect both filtered and unfiltered metals samples.

Because the monitoring wells usually contain little or no water, monitoring the existing wells on a quarterly basis will not adequately detect potential releases from the landfill. One alternative would be to install a monitoring well system in the uppermost aquifer (the regional Troutdale aquifer) as required by 40 CFR 265.90 (a). Another alternative would be to sample the wells, toe drain sump, and underdrain system sump, when there is available water. A rigorous monitoring program should be developed to monitor wells and sumps to determine when there is sufficient water present for the collection of water quality samples. Under this monitoring program, it is very important to obtain water quality samples for the initial pulse of water passing through the waste at the beginning of the wet season. This water is most likely to have the highest concentration of contaminants. One sampling round should be scheduled to coincide with this initial fall flush. Two more sampling rounds should be performed during the wet season when there is sufficient water for sampling (November through March). A fourth round should be attempted after a significant storm event during the dryer part of the year (May through August). If significant concentrations of contaminants are detected in the monitoring wells or the underdrain sump during these rounds of sampling, the facility should install monitoring wells screened in the regional aquifer (Troutdale Formation).

12.0 BIBLIOGRAPHY

- DNA 1988. Groundwater Monitoring Report for the Period November 1987 through May 1988, RBT Landfill Site, Ridgefield, Washington. David J. Newton Associates, Inc. Portland, Oregon. January 1988.
- DNA 1990. Memorandum, Findings based on 1989-1990 data collection, and response to groundwater monitoring concerns letter. David J. Newton Associates, Inc. Portland, Oregon. August 1990.
- DNA 1992. Letter regarding Pacific Wood Treating Corporation, RBT Site, Ridgefield, Washington. June 19, 1992.
- EPA 1983. Test Methods for Chemical Analysis of Water and Wastes. U.S. Environmental Protection Agency, Office of Research and Development. Cincinnati, Ohio.
- EPA 1984. Test Method of Inorganic Anions in Water by Ion Chromatography, Method 300.0. U.S. Environmental Protection Agency. EPA 600/4-84-017. March 1984.
- EPA 1986a. Consent Agreement and Final Order regarding Ridgefield Brick and Tile. U.S. Environmental Protection Agency, Region 10. November 1986.
- EPA 1986b. Groundwater Monitoring Technical Enforcement Guidance Document. OSWER-9950.1. U.S. Environmental Protection Agency. September 1986.
- EPA 1986c. Test Methods for Evaluating Solid Waste, SW-846. Third Edition. U.S. Environmental Protection Agency. November 1986.
- EPA 1988a. Laboratory Data Validation Functional Guidelines for Evaluation of Organic Analyses. U.S. Environmental Protection Agency, Hazardous Site Evaluation Division. February 1988.
- EPA 1988b. Laboratory Data Validation Functional Guidelines for Evaluation of Inorganic Analyses. U.S. Environmental Protection Agency, Hazardous Site Evaluation Division. February 1988.
- EPA 1988c. Operation and Maintenance Inspection Guide, RCRA Groundwater Monitoring Systems. U.S. Environmental Protection Agency, Office of Waste Programs Enforcement. OSWER 9950-3. March 1988.
- EPA 1990a. Drinking Water Regulations and Health Advisories. U.S. Environmental Protection Agency, Office of Drinking Water. Washington D.C. April 1990.
- EPA 1990b. Letter Regarding Clean Closure at the Ridgefield Brick and Tile Site, Ridgefield, Washington. U.S. Environmental Protection Agency. August 10, 1990.
- EPA 1991a. Handbook of Suggested Practices for the Design and Installation of Groundwater Monitoring Wells. U.S. Environmental Protection Agency, Office of Research and Development. Las Vegas, Nevada. EPA/600/4-89/034. March 1991.
- EPA 1991b. Supplemental Risk Assessment Guidance for Superfund. U.S. Environmental Protection Agency, Region 10. August 1991.

Hazard Management Specialists 1987. Closure Plan for Ridgefield Brick and Tile Site, Ridgefield, Washington. February 1987.

PRC 1991. Quality Assurance Project Plan for the Ridgefield Brick and Tile site, Ridgefield, Washington. PRC Environmental Management, Inc. Seattle, Washington. March 1991.

Tetra Tech 1989. Final Report RCRA Comprehensive Groundwater Monitoring Evaluation, Ridgefield Brick and Tile, Ridgefield, Washington. Tetra Tech, Inc. September 1989.

APPENDIX A PHOTOGRAPHIC LOG



Photo No. 1

Date: March 27, 1991

Personnel: Bryant Adams

Mike Buren

Direction Facing: West

Picture Description: Unlocking
monitoring well B-3.



Photo No. 2

Date: March 27, 1991

Personnel: Bryant Adams

Direction Facing: Northwest

Picture Description: Monitoring
well B-7.



Photo No. 3

Date: March 27, 1991

Personnel: Bryant Adams

Direction Facing: Northwest

Picture Description: Measuring water level at monitoring well B-4. A potentially contaminated steel tape used at the PWT shop was used for initial water level measurements at this well.

Photo No. 4



Date: March 27, 1991

Personnel: Mike Buren

Direction Facing: Southwest

Picture Description: Purging monitoring well B-4. Purged groundwater was dumped directly onto the ground surface.

Photo No. 5



Date: March 27, 1991 Personnel: Bryant Adams, Mike Buren Direction Facing: Southwest
Picture Description: Sampling for total metals at monitoring well B-4. Note the high degree of turbidity in the groundwater sample.

Photo No. 6



Date: March 27, 1991 Personnel: Bryant Adams, Mike Buren Direction Facing: Southwest
Picture Description: Field-filtering for dissolved metals at monitoring well B-4. The filter clogged frequently rendering this technique ineffective. Bryant Adams refused to wear gloves during sampling.



Photo No. 7

Date: March 27, 1991

Personnel: Bryant Adams

Direction Facing: Northwest

Picture Description: Monitoring well B-6.

Photo No. 8



Date: March 27, 1991 Personnel: Bryant Adams, Mike Buren Direction Facing: West

Picture Description: Decontaminating bailer at monitoring well B-6.

Photo No. 9



Date: March 27, 1991 Personnel: Bryant Adams, Mike Buren Direction Facing: East

Picture Description: Decontaminating bailer at monitoring well B-5. Decontamination water was poured directly on the ground surface.



Photo No. 10

Date: March 27, 1991

Personnel: Bryant Adams

Direction Facing: West

Picture Description: Decontaminating water-level measuring device at monitoring well B-1.

Photo No. 11



Date: March

27, 1991 Personnel: N/A Direction Facing: N/A

Picture Description: Showing apparatus used to filter groundwater samples for metals analysis. The unit included a funnel, an inline filter, and a cut plastic container used to support the filter system. This system clogged frequently and was eventually abandoned.

Photo No. 12



Date: March 28, 1991 Personnel: Bryant Adams, Mike Buren Direction Facing: Northeast

Picture Description: Purging toe drain standpipe. Discharge was not containerized.

Photo No. 13



Date: March 28, 1991 Personnel: Bryant Adams, Mike Buren Direction Facing: Northwest
Picture Description: Sampling the toe drain standpipe.



Photo No 14

Date: March 28, 1991
Personnel: N/A
Direction Facing: N/A
Picture Description: Collecting standing
water sample TD-1 from the toe drain
standpipe.



Photo No. 15

Date: March 28, 1991

Personnel: N/A

Direction Facing: N/A

Picture Description: Showing inlet of the toe drain, sample location TD-2.


Photo No. 16



Date: March 28, 1991 Personnel: N/A Direction Facing: Southeast

Picture Description: Showing the RBT landfill. The landfill boundary is delineated by a fence.

APPENDIX B POTENTIOMETRIC SURFACE MAPS



FIGURE

1

DAVID J. NEWTON ASSOC.
INCORPORATED
CIVIL & GEOLOGICAL ENGINEERING
1201 S.W. 120th Ave., Suite 800
Portland, Ore. 97205 • 503-771-8100
Branch 767 Willamette St., Suite 506
Eugene, Ore. 97401 • 541-485-1827


PIEZOMETRIC SURFACE Jan 12, 1990

DATE

JULY 1990

PROJECT NO.

212 GE 12 DN



FIGURE


2

DAVID J. NEWTON ASSOC.
INCORPORATED
CIVIL & GEOLOGICAL ENGINEERING
1201 S.W. 12TH AVE., SUITE 620
PORTLAND, ORE. 97205 • 228-7718 • FAX 228-7781
BRANCH 787 WILLAMETTE ST., SUITE 308
EUGENE, ORE. 97401 • 344-0955 • FAX 344-1827

PIEZOMETRIC SURFACE Jan 15, 1990

DATE
JULY 1990

PROJECT NO.
212 GE 12 DN



FIGURE

3

DAVID J. NEWTON ASSOC.
INCORPORATED

CIVIL & GEOLOGICAL ENGINEERING
1201 S.W. 12TH AVE., SUITE 620
PORTLAND, ORE. 97205 • 228-7718 • FAX 228-7781
BRANCH 787 WILLAMETTE ST., SUITE 308
EUGENE, ORE. 97401 • 344-0955 • FAX 344-1827


PIEZOMETRIC
SURFACE
Jan 12, 1990

DATE

JULY 1990

PROJECT NO.

212 GE 12 DN



Scale:
1" = 40'

DAVID J. NEWTON ASSOC.
INCORPORATED
CIVIL & GEOLOGICAL ENGINEERING
1201 S.W. 12TH AVE., SUITE 420
PORTLAND, ORE. 97205 • 228-7718 • FAX 228-7781
BRANCH 787 WILLAMETTE ST., SUITE 308
EUGENE, ORE. 97401 • 344-0855 • FAX 344-1827

**PIEZOMETRIC
SURFACE**
Jan 15, 1990

DATE

JULY 1990

PROJECT NO.
212 GE 12 DN

APPENDIX C PRC FIELD NOTES

Ridgefield
Brick and Tile

Ridgefield,
Washington

Operator and
Maintenance
Inspector

March 27 and 28,
1991

3/27/91 Arrive on site
8:50 AM.

Bryant Adams
Pacific Wood Treating
Corp.
Ridgefield

Mike Dura
David Newton Assoc.

#24 Well B-2

#23 Well B-3

#22 Well B-3

water level measurement
.69 feet deep.

Bryant Adams
measured Well B-3
on 3/26, too low
to purge and
sample.

#4 and 5
purged yesterday
3/26 using trailer.

#21 Well B-4 opening
20 decontaminating
probe using D-I
water.

measured 1' using
steel tape in

4.12 ft to WIL

rinsed steel tape
w/ with D-I water.

LUFRIN tape.

#18 Well B-6

17 Well B-6 w/
measurement

39.65 feet deep w/l.

#16

Well B-1 (time 10:12)

decontaminating

probe. by

rinsing with

D-I water

dry well. - only 2-3 inches
(.75 ft)

on 3/26 the well B-6

had 3 ft water

#15-14-13

sense of
landfill.

#12

Well B-5

on 3/26 32 ft. water.

3/27 3 ft water.

#11

Well B-7 (10:36)

usually only has

high water

historically

about 4 inches .34 feet.

some kind of larva

on probe. after

removing from well

RBTs parameter
PAH
Chlorophylls
Arsenic
Chromium.

11:15 PRC took equipment
unsat sample
of barite.

Barite was characterized
in the PWT Lab.
before coming in for it.

RB-B15-01

11:50 45 micron filter
quick filter
high capacity
(QED - FF-4200
(environmental systems)
clogged put mouth

over filter tube to suck
water through

Bar F.

unknown filter element
appropriate? Yes

water cloudy with particulate
makesh-ft 'stand'
not used for anything else

11:50 begin collecting
filtered metals
samples

ground water very
cloudy.

RBT attempted to
collect filtered
metals sample
using inline filter
and percol. did
not work.

PRC used Nalgene
filtering equipment.

decided to collect
filtered metals
first due to
turbidity in
water in w/60 diam
from well.

~~#20~~ collect total
metals next
RB-B4-01

RB-B4-01 MS/MSD

RB-B10-01 duplicate
at well B-4.

due to concern for
enough ground
water available
from the well B-4
for all samples,
MS/MSD duplicate,
PRC decided to
collect only 3 1-L
containers for
each sample
type.

Sample RB-B4-01	3	1-L
MS	"	3 1-L
MSD	"	3 1-L
duplicate of B4		
RB-B10-01	3	1-L

after collecting 9 1-L
containers for PAH
ROT took its sample
for TOC and
specific cond, pH.
fluoride, chloride, sulfate

Nitrate, turbidity.

— Labt 3 chlorophenol/PAH
taken after B10 samples
about 1245.

145 RBT took lunch
break

115 Purged 3 volumes
from well B-6.
will let recover
and return after lunch.

300 pm.

move to well B-5.
Services
Columbia Analytical Lab

PO Box 479 Kelso WA 98626

#5 } well B-5
#4 }

order: VOA ~~1 liter~~
PAH 1 liter
chlorophenol 1 liter

Alternated samples with
RBT.

(on top of ball) Sand - very turbid
caused bailer to
misfunction

1315 moved to well
B6 so as to
let B5 recover

#3 well B-6

1520 took VIA RB-86-01
PAH 1 L

RBT took PAH 1 L

ground-water clear.
PCC Chlorophenol $\frac{1}{2}$ L

1600 moved back to well
B5 to let

B-6 recover

- rinsed bailer with black water
- RBT finisher its
collection of para-
chlorophenol 1 L
sample.

water very turbid
with silt in bailer

after a few bails,
well dry.

Note on grounds around
landfill area. Brown
vegetated but swampy
on all sides of
landfill but
east up gradient
(up hill) side

1610 move back to
well B6.

rinsed bailer with
black water

Water marker
Water level indicator
Johnson Division VOP

1740

Curious bystander
Disorganized samples - different samples,
mixed with trash, lunch,
bags etc.

3/28/91

0745 Arrived on RBT site
met Bryant Adams

mobilized to Toe Drain
to begin sampling

Weather overcast and
sprinkling.

8:25 Facility samples

Jumbled not stored papers
cooled overnight with minimal
ice

0830 moved to well B-6
to continue sampling

39.66 feet today to water
so about $2\frac{1}{2}$ ft water.

HB

RBT rinsed ~~in~~ ⁱⁿ line
with D-I water and
line before starting.

Mike of David Newton Assoc.
wears gloves.

non-indelible on labels

930 ② PRE collected total
metals and dissolved
metals samples
RB-B6-01

① RBT collected 1-L
sample for
serum chlorophenol.

③ RBT collected metals
sample.

~~Are plastic bottles~~ ~~Q.F.~~ Q.F.

RBT collects
④ metals sample for
dissolved metals
using inline filter
rigged with funnel.

RBT collects TOC sample

900 PRE collects PAH
sample to continue
previous day's sample.

930 moved to TOC drain

RBT used bailer to
collect standing
leachate.

Rinsed bailer with
D-I water before
starting.

PRC collected

RB-TD1-01

6 VOC

12 PAH 1-L

12 Chlorophenols 1-L

2 Total metals

2 Dissolved metals

1015 ~~RB~~ RB-TD10-01

4 PAH 1-L

4 Chlorophenol 1-L

2 metals

1 total

1 dissolved

1030 begin toe drain
purge

inlet pipe
gushing water
very fast
into toe drain.

PRC collected

4 PAH 1-L

4 Chlorophenol 1-L

1 Total metal

1 Dissolved metal

2 VOC vials

RBT collected

PAH - TOC

Penta - pH, SC

Total metal

Dissolved metals -

filtered in lab.

finish 1105 toe drain

1110 place toe drain
cover back in
place.

PRC's samples
from inlet pipe
in toe drain were
collected by RBT
who went down
ladder into drain.

VOA samples were
collected from
the fast moving
inlet stream by
carefully holding
vial at edge of
stream. Collected
with no headspace
or bubbles.

All other PRC
samples also

collected from
inlet stream.
by RBT.

1125 collected VOA
equipment rinsate
RA-TD15-01
91130168

PHIT
Chlorophenol
Total Phthalate
Monobutyl Phthalate

1200 PRC collected
field transfer
blank by pouring
HPLC water into
preserved VOA vials
(ACI)

1215 left side

requested final
information for
RBT.

7

B

APPENDIX D OPERATION AND MAINTENANCE FIELD INSPECTION CHECKLIST

4. Observe the owner/operator's staff as they collect ground-water samples at several wells. Complete the following table for each well (Note: revise or add to the table if permit conditions dictate a different requirement the owner/operator must follow):

Position/Title	Name	Sampling Experience (years and type)
Geologist	Mike Buren	< 1 yr. environmental
Environmental Manager	Bryant Adams	1 yr. environmental

Well Identification Number <u>B-4</u>	Y/N	Photograph Taken Y/N
Did the sampling crew measure static water levels in the well and well depths prior to the sampling event?	Y	Y
Did the sampling crew use a steel tape or electronic device to take depth measurements?	Y	Y
Did the sampling crew record depths to +/- 0.01 feet?	N	Y
Did the sampling crew follow these procedures: 1. remove locking and protective cap; 2. sample the air in the well head for organic vapors; 3. determine the static water level; and 4. lower an interface probe into the well to detect immiscible layers.	N	N
If immiscible samples were collected, were they collected prior to well purging?	NA	—
Did the sampling crew evacuate low yielding wells to dryness prior to sampling?	Y	—
Did sampling crew evacuate high yielding wells so that at least three casing volumes were removed?	Y	Y
Did the sampling crew collect the purge water for storage and analysis or for shipment off-site to a RCRA treatment facility?	N	N
Were sampling devices constructed of fluorocarbon resins or stainless steel?	FR	Y

NA = not applicable

(Continued)

Well Identification Number <u>B-7</u>	Y/N	Photograph Taken Y/N
If the sampling crew used dedicated samplers, did they disassemble and thoroughly clean the devices between samples?	NA	
If samples are collected for organic analyses, did the cleaning procedure include the following steps: <ol style="list-style-type: none"> 1. non phosphate detergent wash 2. tap water rinse 3. distilled/deionized water rinse 4. acetone rinse 5. pesticide-grade hexane rinse? 	N	Y
If samples are collected for inorganic analyses, does the cleaning procedure include the following steps: <ol style="list-style-type: none"> 1. dilute acid rinse (HNO₃ or HCL) 2. distilled/de-ionized water rinse? 	N	N
Did the sampling crew take trip blanks, field blanks and equipment blanks?	N	N
If the sampling crew used bailers, were they bottom valve bailers?	N	Y
If the sampling crew used bailers, was "teflon" coated wire, single strand stainless steel wire or monofilament used to raise and lower the bailer?	N	Y
If the sampling crew used bailers, did they lower the bailer slowly to the well?	Y	N
If the sampling crew used bailers, were the bailer contents transferred to the sample container to minimize agitation and aeration?	Y	Y
Did the sampling crew take care to avoid placing clean sampling equipment, hoses, and lines on the ground or other contaminated surfaces prior to insertion in the well?	N	Y
If the sampling crew used dedicated bladder pumps: <p>Was the compressed gas from an oilless compressor certified quality commercial compressed gas cylinder? If not, was a suitable oil removal purification system installed and maintained?</p>	NA	
Was the bladder pump controller capable of throttling the bladder pump discharge flow to 100 ml/min or less for continuous periods of at least 20-30 seconds without restricting liquid discharge?	NA	

(Continued)

Well Identification Number <u>B-4</u>	Y/N	Photograph Taken Y/N
Were samples taken from the bladder pump discharge tube, and not from any purge device discharge tube?	NA	
Was the bladder pump discharge flow checked for the presence of gas bubbles before each sample collection, as a test for bladder integrity?	NA	
Was bladder pump flow performance monitored regularly for dropoff in flow rate and discharge volume per cycle?	NA	
Was the bladder pump incorporated in a combination sample-purge pump design which can expose the bladder pump interior and discharge tubing to the pump drive gas? If so, were operating procedures established and followed to prevent at all times the entry of drive gas into the sample flow or into the bladder pump interior?	NA	
Did the sampling crew collect and containerize samples in the order of the volatilization sensitivity of the parameters?	BF NA N	N
Did the sampling crew measure the following parameters in the field: pH, temperature, specific conductance?	BF NA N	N
Did the sampling crew sample background wells before sampling downgradient wells?	NA N	—
Did the sampling crew use fluorocarbon resin or polyethylene containers with polypropylene caps for samples requiring metals analysis?	BF NA Y	Y
Did the sampling crew use glass bottles with fluorocarbon resin-lined caps for samples requiring metals analysis?	N	NA Y
If metals were the analytes of concern, did the sampling crew use containers cleaned with nonphosphate detergent and water, and rinsed with nitric acid, tap water, hydrochloric acid, tap water and finally Type II water?	unknown	N BF
If organics were the analytes of concern, did the sampling crew use containers cleaned with nonphosphate detergent, rinsed with tap water, distilled water, acetone, and finally pesticide quality hexane?	unknown	N BF
Did the sampling crew filter samples requiring analysis for organics?	N	NA BF N

APPENDIX E RBT ANALYTICAL DATA SUMMARY



April 18, 1991

Bryant Adams
Pacific Wood Treating
111 West Division St.
Ridgefield, WA 98642

Re: RBT - PWT Corp. Project

Dear Bryant:

Enclosed are the results of the water samples submitted to our lab on March 28, 1991. For your reference, our service request number for this work is K911619.

All analyses were performed in accordance with the laboratory's quality assurance program.

Please call if you have any questions.

Respectfully submitted,

Columbia Analytical Services, Inc.

A handwritten signature in dark ink, appearing to read "David L. Edelman".

David L. Edelman
Vice-President

DLE/das

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Work Order #: K911619

Inorganic Parameters
mg/L (ppm)

Sample Name:	24	26, 3/27	28, 3/28
Lab Code:	K1619-1	K1619-3	K1619-4

Analytes	Method	MRL			
pH	150.1	-	7.99	6.34	6.28
Conductivity (μ mhos/cm)	120.1	2	146	367	288
Chloride	300.0	0.2	5.3	1.3	1.2
Fluoride	300.0	0.2	0.2	ND	ND
Nitrogen, Nitrate	300.0	0.2	0.2	0.3	0.3
Sulfate	300.0	0.2	3.0	4.0	3.8
Total Organic Carbon (TOC)	415.1	0.5	2.5	1.1	1.8
Turbidity (NTU)	180.1	1	340	43	32

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

Approved by Dave Schellman Date 4/18/91

00001

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Pacific Wood Treating
 Submitted By: Bryant Adams
 Project: RBT - PWT Corp.
 Sample Matrix: Water

Date Received: 03/28/91
 Work Order #: K911619

**Inorganic Parameters
 mg/L (ppm)**

Sample Name:
 Lab Code:

29
 K1619-6

Method Blank
 K1619-MB

Analytes	Method	MRL		
pH	150.1	.	8.04	-
Conductivity (μ mhos/cm)	120.1	2	115	ND
Chloride	300.0	0.2	3.1	ND
Fluoride	300.0	0.2	ND	ND
Nitrogen, Nitrate	300.0	0.2	ND	ND
Sulfate	300.0	0.2	4.9	ND
Total Organic Carbon (TOC)	415.1	0.5	2.5	ND
Turbidity (NTU)	180.1	1	25	ND

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

Approved by Dave E. Johnson Date 4/18/91

00002

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Work Order #: K911619

**Dissolved Metals
mg/L (ppm)**

Analytes:	Chromium	Arsenic
Method:	6010	7060
Method Reporting Limit:	0.005	0.005

Sample Name	Lab Code		
24	K1619-1	ND	ND
26 3/28	K1619-4	ND	ND
29	K1619-6	ND	ND
Method Blank	K1619-MB	ND	ND

ND None Detected at or above the method reporting limit

Approved by Dave Edelinger Date 4/18/91

00003

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Date Extracted: 04/03/91
Date Analyzed: 04/09/91
Work Order #: K911619

Polynuclear Aromatic Hydrocarbons
EPA Methods 3510/8100
 $\mu\text{g/L}$ (ppb)

Sample Name:	24	25	26 3/27
Lab Code:	K1619-1	K1619-2	K1619-3

Analytes	MRL			
Naphthalene	1	ND	ND	ND
Acenaphthylene	1	ND	ND	ND
Acenaphthene	1	ND	ND	ND
Fluorene	1	ND	ND	ND
Phenanthrene	1	ND	ND	ND
Anthracene	1	ND	ND	ND
Fluoranthene	1	ND	ND	ND
Pyrene	1	ND	ND	ND
Benzo(a)anthracene	1	ND	ND	ND
Chrysene	1	ND	ND	ND
Benzo(b + k)fluoranthene*	2	ND	ND	ND
Benzo(a)pyrene	1	ND	ND	ND
Indeno(1,2,3-cd)pyrene and Dibenzo(a,h)anthracene*	2	ND	ND	ND
Benzo(g,h,i)perylene	1	ND	ND	ND

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

* Compounds co-elute; therefore, the results are reported as the combined concentration.

Approved by Dave Ehlman Date 4/18/91

00004

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Date Extracted: 04/03/91
Date Analyzed: 04/09/91
Work Order #: K911619

Polynuclear Aromatic Hydrocarbons
EPA Methods 3510/8100
µg/L (ppb)

Sample Name: 26 3/28 29 Method Blank
Lab Code: K1619-4 K1619-6 K1619-MB

Analytes	MRL			
Naphthalene	1	ND	ND	ND
Acenaphthylene	1	ND	ND	ND
Acenaphthene	1	ND	ND	ND
Fluorene	1	ND	ND	ND
Phenanthrene	1	ND	ND	ND
Anthracene	1	ND	ND	ND
Fluoranthene	1	ND	ND	ND
Pyrene	1	ND	ND	ND
Benzo(a)anthracene	1	ND	ND	ND
Chrysene	1	ND	ND	ND
Benzo(b + k)fluoranthene*	2	ND	ND	ND
Benzo(a)pyrene	1	ND	ND	ND
Indeno(1,2,3-cd)pyrene and Dibenzo(a,h)anthracene*	2	ND	ND	ND
Benzo(g,h,i)perylene	1	ND	ND	ND

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

* Compounds co-elute; therefore, the results are reported as the combined concentration.

Approved by Dave Edelman Date 4/18/91

00005

COLUMBIA ANALYTICAL SERVICES, INC.

Analytical Report

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Date Extracted: 03/29/91
Date Analyzed: 04/01/91
Work Order #: K911619

Chlorinated Phenolic Compounds
EPA Methods 3510/Modified 8150
 $\mu\text{g/L}$ (ppb)

Sample Name	Lab Code	MRL	Total Tetrachloro- phenols	Pentachloro- phenol
24	K1619-1	5	ND	ND
25	K1619-2	5	ND	ND
26 3/27	K1619-3	5	ND	ND
26 3/28	K1619-4	5	ND	ND
29	K1619-6	5	ND	ND
Method Blank	K1619-MB	5	ND	ND

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

Approved by Dave Edelstein Date 4/13/91

00006

APPENDIX A
LABORATORY QC RESULTS

00007

COLUMBIA ANALYTICAL SERVICES, INC.

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Work Order #: K911619

QA/QC Report
Duplicate Summary
Dissolved Metals
mg/L (ppm)

Sample Name: 24
Lab Code: K1619-1

Analytes	Method	MRL	Sample Result	Duplicate Sample Result	Average	Relative Percent Difference
Arsenic	7060	0.005	ND	ND	ND	--
Chromium	8010	0.005	ND	ND	ND	--

MRL Method Reporting Limit

ND None Detected at or above the method reporting limit

Approved by Dave Edelmann

Date 4/18/91

00008

COLUMBIA ANALYTICAL SERVICES, INC.

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Work Order #: K911619

QA/QC Report
 Matrix Spike Summary
 Dissolved Metals
 mg/L (ppm)

Sample Name: 24
Lab Code: K1619-1MS

Analytes	MRL	Spike Level	Sample Result	Spiked Sample Result	Percent Recovery
Arsenic	0.005	0.04	ND	0.042	105
Chromium	0.005	0.2	ND	0.196	98

MRL Method Reporting Limit
ND None Detected at or above the method reporting limit

Approved by Dave Selmon Date 4/18/91

00009

COLUMBIA ANALYTICAL SERVICES, INC.

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Date Extracted: 04/03/91
Date Analyzed: 04/09/91
Work Order #: K911619

QA/QC Report
Surrogate Recovery Summary
Polynuclear Aromatic Hydrocarbons
EPA Methods 3510/8100

Sample Name	Lab Code	Percent Recovery <i>p</i> -Terphenyl
24	K1619-1	64.3
25	K1619-2	48.8
26 3/27	K1619-3	77.5
28 3/28	K1619-4	73.6
29	K1619-6	75.7
Method Blank	K1619-MB	35.9

CAS Acceptance Criteria 35-105

Approved by Dave Schlemmer Date 4/18/91

00010

COLUMBIA ANALYTICAL SERVICES, INC.

Client: Pacific Wood Treating
Submitted By: Bryant Adams
Project: RBT - PWT Corp.
Sample Matrix: Water

Date Received: 03/28/91
Date Extracted: 03/29/91
Date Analyzed: 04/01/91
Work Order #: K911619

QA/QC Report
Surrogate Recovery Summary
Chlorinated Phenolic Compounds
EPA Methods 3510/Modified 8150

Sample Name	Lab Code	Percent Recovery 4-Bromo-2,6-dichlorophenol
24	K1619-1	78.0
25	K1619-2	66.7
26 3/27	K1619-3	80.9
26 3/28	K1619-4	82.8
29	K1619-6	77.8
29	K1619-6MS	87.7
29	K1619-6DMS	84.6
Method Blank	K1619-MB	89.2

CAS Acceptance Criteria 60-125

Approved by Dave Edelman Date 4/18/91

COLUMBIA ANALYTICAL SERVICES, INC.

Client: Pacific Wood Treating
 Submitted By: Bryant Adams
 Project: RBT - PWT Corp.
 Sample Matrix: Water

Date Received: 03/28/91
 Date Extracted: 03/29/91
 Date Analyzed: 04/01/91
 Work Order #: K911619

QA/QC Report
Matrix Spike/Duplicate Matrix Spike Summary
Chlorinated Phenolic Compounds
EPA Methods 3510/Modified 8150
 $\mu\text{g/L}$ (ppb)

Sample Name: 29
 Lab Code: K1619-6MS/DMS

Analytes	Spike Level		Sample Result	Spike Result		Percent Recovery		
	MS	DMS		MS	DMS	MS	DMS	CAS Acceptance Criteria
Total Tetrachlorophenols	300	300	ND	256	250	85.3	83.3	50-120
Pentachlorophenol	150	150	ND	127	124	84.7	82.7	55-120

ND None Detected at or above the method reporting limit

Approved by Dave Schuman Date 4/18/91

00012

APPENDIX B
CHAIN OF CUSTODY INFORMATION

00013



Chain of Custody/ Laboratory Analysis Request

1317 South 13th Avenue • Kelso, WA 98626 • 206/577-7222, Fax 206/636-1068

DATE 28 Mar 91 PAGE 1 OF 1

PROJECT <u>RBT - PWT Corp.</u>					ORGANIC ANALYSIS										INORGANIC ANALYSIS					OTHER		NUMBER OF CONTAINERS	
SEND REPORT TO <u>Bryant Adams</u>					Baseflow/Acid Organics GC/MS 821/8270	Volatile Organics GC/MS 824/8240	Halogenated Volatiles 801/8010	Aromatic Volatiles 802/8020 BTEX	Gas/PTX 1000 8015/8020	Pesticides/PCBs 806/8060	Total Petroleum Hydrocarbons - Mod 8015	Total Petroleum Hydrocarbons - 418.1	Total Organic Halides (TOX) 8020	Total Organic Carbon (TOC) 418/8060	EPTOX Metals As, Ba, Cd, Cr, Pb, Hg, Se, Ag	Metals (total or dissolved) * List Below <u>As, Cr, Pb</u>	Cyanide	Ph. Cond. Cl, SO ₄ , NO ₃ , F, PO ₄ 418/8016	NH ₄ -N, CO ₃ , Total-P, TKN (Circle)	Coliform Total, Fecal	PAHs		Pesticides
SAMPLE ID.	DATE	TIME	LAB ID.	MATRIX																			
1. 24	3/27/91													✓		✓		✓			✓	✓	5
2. 25	3/27/91													✓		✓		✓			✓	✓	5
3. 26	3/27/91													✓		✓		✓			✓	✓	5
4. 26	3/28/91													✓	✓	✓		✓			✓	✓	5
5. 29	3/28/91													✓	✓	✓		✓			✓	✓	5
6. 28	3/28/91													✓	✓	✓		✓			✓	✓	5
7.																							
8.																							

Relinquished By		Relinquished By		Invoice Information:		Project Information		Sample Receipt	
Signature <u>Bryant L. Adams</u>	Signature	P.O.#	Site Contact:	Shipped Via:					
Printed Name	Printed Name	BILL to:	Site Address:	Seals Intact:					
Firm	Firm			Condition:					
Date/Time <u>12:42</u>	Date/Time			Lab No.					
Received By: <u>Kathleen</u>	Received By:	Special Instruction/Comments:		SR Number:					
Signature	Signature	To sampler - Mike Baum David Newson & Assoc.							
Printed Name <u>Kathleen</u>	Printed Name	Sampling observed by - GMB of PRC							
Firm <u>CAS</u>	Firm	* Filter Metals at Lab							
		metals btl's 10619 & 5 can't be filtered at lab, already							

K1619

NUMBER OF CONTAINERS

5

5

5

5

APPENDIX F EPA ANALYTICAL DATA SUMMARY

Below are the definitions for qualifiers used in the Metals area when qualifying data from metals analysis.

Data Qualifiers

- | | | |
|-----|---|--|
| U | - | Element was analyzed for but not detected. The associated numerical value is the instrument detection limit/method detection limit. |
| J | - | The analyte was detected above the instrument detection limit but not quantified within expected limits of precision. The laboratory has established minimum quantitation limits having a relative standard deviation of no more than 10%. |
| E | - | The reported value is an estimate because of the presence of interference. |
| B | - | Analyte found in the analytical blank as well as the sample, indicating possible/probable contamination. "B" accompanies those analytical results within 10 (10x) times the instrument detection limit for the analyte of interest. |
| N | - | Spike sample recovery not within control limits. |
| NAR | - | There is <u>no analysis result</u> for this analyte. |
| NA | - | Not Applicable/Not Required. |
| * | - | The analyte was present in the sample. |

Qualifier and Remark Codes
for
Manchester Environmental Laboratory Generated Data

Qualifier remark code	Definition
"B"	Analyte was also found in the analytical method blank indicating the sample may have been contaminated. (Not used when reporting organic data.)
"EXP"	The result is equal to the number before EXP times 10 to the power of the number after EXP. As an example 3EXP6 equals 3×10^6 .
"E"	Reported result is an estimate because of the presence of interference. (Not used when reporting organic data.)
"J"	The analyte was positively identified. The associated numerical result is an <u>estimate</u> .
"N"	For organic analytes there is evidence the analyte is present in this sample. For metals analytes the spike sample recovery is not within control limits.
"NJ"	There is evidence that the analyte is present. The associated numerical result is an estimate.
"NAF"	Not analyzed for.
"p"	The analyte was detected above the instrument detection limit but below the established minimum quantitation limit. (Not used when reporting organic data.)
"REJ"	The data are <u>unusable</u> for all purposes.
"U"	The analyte was not detected at or above the reported result.
"UJ"	The analyte was not detected at or above the reported estimated result.
"*"	The analyte was present in the sample. (Visual Aid to locate detected compound on report sheet.)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130150

Description: RB-B15-01 (Equipment rinsate blanks)

Source: Well (Test/Observation)

Begin Date: 91/03/27 11:15

Metals - Specified			Water-Total		VOA - PP Scan (GCMS)			Water-Total		B/N/Acid Scan			Water-Total	
			Result	Units	*** Continued ***			Result	Units	*** Continued ***			Result	Units
Arsenic	As-Total	1.5U	ug/l											
Chromium	Cr-Total	0.4JB*	ug/l											

(Sample Complete)

11:41:40

Sample/Project Analysis Results

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130151

Description: RB-B15-01

(Equipment Air-side Blank)

Source: Well (Test/Observation)

Begin Date: 91/03/27 11:15

Metals - Specified		Water-Filtere	
		Result	Units
Arsenic	As-Diss	1.5U	ug/l
Chromium	Cr-Diss	0.2JB*	ug/l

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130152

Description: RB-B4-01

Source: Well (Test/Observation)

Begin Date: 91/03/27 12:30

Metals - Specified			VOA - PP Scan (GCMS)			VOA - PP Scan (GCMS)		
Water-Total			Water-Total			Water-Total		
Result Units			Result Units			Result Units		
Matrix Spike #1			Matrix Spike #1			Matrix Spike #1		
Arsenic	As-Total	1.8J* ug/l	Hexachlorobutadiene	1U	ug/l	Carbon Tetrachloride	84	% Recov
Chromium	Cr-Total	15.6 * ug/l	Naphthalene	1U	ug/l	Acetone	150	% Recov
			2-Chlorotoluene	1U	ug/l	Chloroform	89	% Recov
			1,2-Dichlorobenzene	1U	ug/l	Benzene	84	% Recov
			1,2,4-Trimethylbenzene	1U	ug/l	1,1,1-Trichloroethane	88	% Recov
			1,2-Dibromo-3-chloropr+	1U	ug/l	Bromomethane	69	% Recov
			1,2,3-Trichloropropane	1U	ug/l	Chloromethane	65	% Recov
			Tert-Butylbenzene	1U	ug/l	Dibromomethane	90	% Recov
			Isopropylbenzene (Cume+	1U	ug/l	Bromochloromethane	86	% Recov
			p-Isopropyltoluene	1U	ug/l	Chloroethane	70	% Recov
			Ethylbenzene	1U	ug/l	Vinyl Chloride	68	% Recov
			BENZENE, ETHENYL-(STYR+	1U	ug/l	Methylene Chloride	96	% Recov
			BENZENE, PROPYL-	1U	ug/l	Carbon Disulfide	68	% Recov
			Butylbenzene	1U	ug/l	Bromoform	90	% Recov
			4-Chlorotoluene	1U	ug/l	Bromodichloromethane	86	% Recov
			1,4-Dichlorobenzene	1U	ug/l	1,1-Dichloroethane	88	% Recov
			1,2-Dibromoethane (EDB)	1U	ug/l	1,1-Dichloroethene	75	% Recov
			1,2-Dichloroethane	0.8J*	ug/l	Trichlorofluoromethane	67	% Recov
			4-Methyl-2-Pentanone	1U	ug/l	Methane, Dichlorodiflu+	58	% Recov
			1,3,5-Trimethylbenzene	1U	ug/l	1,2-Dichloropropane	84	% Recov
			Bromobenzene	1U	ug/l	2-Butanone	83	% Recov
			Toluene	1U	ug/l	1,1,2-Trichloroethane	87	% Recov
			Chlorobenzene	1U	ug/l	Trichloroethene	88	% Recov
			1,2,4-Trichlorobenzene	1U	ug/l	ETHANE, 1,1,2,2-TETRAC+	88	% Recov
			Dibromochloromethane	1U	ug/l	1,2,3-Trichlorobenzene	112	% Recov
			Tetrachloroethene	1U	ug/l	Hexachlorobutadiene	90	% Recov
			Sec-Butylbenzene	1U	ug/l	Naphthalene	125	% Recov
			1,3-Dichloropropane	1U	ug/l	2-Chlorotoluene	87	% Recov
			Cis-1,2-Dichloroethene	1U	ug/l	1,2-Dichlorobenzene	87	% Recov
			trans-1,2-Dichloroethe+	1U	ug/l	1,2,4-Trimethylbenzene	84	% Recov
			1,3-Dichlorobenzene	1U	ug/l	1,2-Dibromo-3-chloropr+	99	% Recov
			1,1-Dichloropropene	1U	ug/l	1,2,3-Trichloropropane	80	% Recov
			2,2-Dichloropropane	1U	ug/l	Tert-Butylbenzene	81	% Recov
			2-Hexanone	1U	ug/l	Isopropylbenzene (Cume+	80	% Recov
			Ethane, 1,1,1,2-Tetrac+	1U	ug/l	p-Isopropyltoluene	81	% Recov
			Total Xylenes	1U	ug/l	Ethylbenzene	80	% Recov
			cis-1,3-Dichloropropene	1U	ug/l	BENZENE, ETHENYL-(STYR+	80	% Recov
			trans-1,3-Dichloroprop+	1U	ug/l	BENZENE, PROPYL-	82	% Recov
			p-Bromofluorobenzene	98	% Recov	Butylbenzene	83	% Recov
			Surrog: 1-Bromo-2-Fluo+	111	% Recov	4-Chlorotoluene	88	% Recov
			d8-Toluene	100	% Recov	1,4-Dichlorobenzene	92	% Recov
			d4-1,2-Dichlorobenzene+	NAF	% Recov	1,2-Dibromoethane (EDB)	88	% Recov
			1,2-Dichloroethane-d4 +	104	% Recov	1,2-Dichloroethane	48	% Recov
						4-Methyl-2-Pentanone	98	% Recov
						1,3,5-Trimethylbenzene	81	% Recov

(Continued on next page)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130152

Description: RB-B4-01

Source: Well (Test/Observation)

Begin Date: 91/03/27 12:30

+-----+ VOA - PP Scan (GCMS) Water-Total *** Continued *** Matrix Spike #1 Result Units +-----+			+-----+ VOA - PP Scan (GCMS) Water-Total *** Continued *** Matrix Spike #2 Result Units +-----+			+-----+ VOA - PP Scan (GCMS) Water-Total *** Continued *** Matrix Spike #2 Result Units +-----+		
Bromobenzene	86	% Recov	1,1-Dichloroethene	90	% Recov	Total Xylenes	81	% Recov
Toluene	87	% Recov	Trichlorofluoromethane	96	% Recov	d8-Toluene	96	% Recov
Chlorobenzene	86	% Recov	Methane, Dichlorodiflu+	37	% Recov	cis-1,3-Dichloropropene	75	% Recov
1,2,4-Trichlorobenzene	106	% Recov	1,2-Dichloropropane	80	% Recov	trans-1,3-Dichloroprop+	72	% Recov
Dibromochloromethane	83	% Recov	2-Butanone	78	% Recov	p-Bromofluorobenzene	101	% Recov
Tetrachloroethene	88	% Recov	1,1,2-Trichloroethane	78	% Recov	Surrog: 1-Bromo-2-Fluo+	98	% Recov
Sec-Butylbenzene	78	% Recov	Trichloroethene	82	% Recov	d4-1,2-Dichlorobenzene+	NAF	% Recov
1,3-Dichloropropane	85	% Recov	ETHANE, 1,1,2,2-TETRAC+	84	% Recov	1,2-Dichloroethane-d4 +	98	% Recov
Cis-1,2-Dichloroethene	84	% Recov	1,2,3-Trichlorobenzene	102	% Recov			
trans-1,2-Dichloroethe+	80	% Recov	Hexachlorobutadiene	92	% Recov	+-----+ B/N/Acid Scan Water-Total Result Units +-----+		
1,3-Dichlorobenzene	90	% Recov	Naphthalene	98	% Recov	Benzo(a)pyrene	0.03J*	ug/l
1,1-Dichloropropane	81	% Recov	2-Chlorotoluene	88	% Recov	2,4-Dinitrophenol	0.06UJ	ug/l
2,2-Dichloropropane	86	% Recov	1,2-Dichlorobenzene	88	% Recov	Dibenzo(a,h)anthracene	0.06UJ	ug/l
2-Hexanone	90	% Recov	1,2,4-Trimethylbenzene	83	% Recov	Benzo(a)anthracene	0.06UJ	ug/l
Ethane, 1,1,1,2-Tetrac+	89	% Recov	1,2-Dibromo-3-chloropr+	93	% Recov	4-Chloro-3-Methylphenol	0.06UJ	ug/l
Total Xylenes	80	% Recov	1,2,3-Trichloropropane	80	% Recov	Acenaphthene	0.0006J*	ug/l
d8-Toluene	98	% Recov	Tert-Butylbenzene	82	% Recov	Phenanthrene	0.005J*	ug/l
cis-1,3-Dichloropropene	79	% Recov	Isopropylbenzene (Cume+	80	% Recov	Fluorene	0.06UJ	ug/l
trans-1,3-Dichloroprop+	78	% Recov	p-Isopropyltoluene	80	% Recov	Carbazole	0.02J*	ug/l
p-Bromofluorobenzene	99	% Recov	Ethylbenzene	81	% Recov	Pentachlorophenol	0.02J*	ug/l
Surrog: 1-Bromo-2-Fluo+	107	% Recov	BENZENE, ETHENYL-(STYR+	82	% Recov	2,4,6-Trichlorophenol	0.06UJ	ug/l
d4-1,2-Dichlorobenzene+	NAF	% Recov	BENZENE, PROPYL-	84	% Recov	2-Nitrophenol	0.06UJ	ug/l
1,2-Dichloroethane-d4 +	101	% Recov	Butylbenzene	80	% Recov	Naphthalene, 1-Methyl-	0.06UJ	ug/l
+-----+ VOA - PP Scan (GCMS) Water-Total Matrix Spike #2 Result Units +-----+			4-Chlorotoluene	86	% Recov	Naphthalene	0.06UJ	ug/l
Carbon Tetrachloride	86	% Recov	1,4-Dichlorobenzene	90	% Recov	2-Methylnaphthalene	0.002J*	ug/l
Acetone	126	% Recov	1,2-Dibromoethane (EDB)	78	% Recov	2-Chloronaphthalene	0.06UJ	ug/l
Chloroform	88	% Recov	1,2-Dichloroethane	45	% Recov	2-Methylphenol	0.06UJ	ug/l
Benzene	80	% Recov	4-Methyl-2-Pentanone	83	% Recov	o-Chlorophenol	0.06UJ	ug/l
1,1,1-Trichloroethane	83	% Recov	1,3,5-Trimethylbenzene	80	% Recov	2,4,5-Trichlorophenol	0.06UJ	ug/l
Bromomethane	94	% Recov	Bromobenzene	87	% Recov	4-Nitrophenol	0.6UJ	ug/l
Chloromethane	80	% Recov	Toluene	81	% Recov	2,4-Dimethylphenol	0.06UJ	ug/l
Dibromomethane	78	% Recov	Chlorobenzene	86	% Recov	4-Methylphenol	0.003J*	ug/l
Bromochloromethane	88	% Recov	1,2,4-Trichlorobenzene	96	% Recov	Phenol	0.06UJ	ug/l
Chloroethane	91	% Recov	Dibromochloromethane	80	% Recov	Anthracene	0.06UJ	ug/l
Vinyl Chloride	80	% Recov	Tetrachloroethene	83	% Recov	2,4-Dichlorophenol	0.06UJ	ug/l
Methylene Chloride	123	% Recov	Sec-Butylbenzene	80	% Recov	Pyrene	0.02J*	ug/l
Carbon Disulfide	85	% Recov	1,3-Dichloropropane	78	% Recov	Dibenzofuran	0.001J*	ug/l
Bromoform	84	% Recov	Cis-1,2-Dichloroethene	84	% Recov	Benzo(ghi)perylene	0.06UJ	ug/l
Bromodichloromethane	82	% Recov	trans-1,2-Dichloroethe+	90	% Recov	Indeno(1,2,3-cd)pyrene	0.06UJ	ug/l
1,1-Dichloroethane	94	% Recov	1,3-Dichlorobenzene	88	% Recov	Benzo(b)fluoranthene	0.04J*	ug/l
			1,1-Dichloropropene	80	% Recov	Fluoranthene	0.01J*	ug/l
			2,2-Dichloropropane	90	% Recov			
			2-Hexanone	78	% Recov			
			Ethane, 1,1,1,2-Tetrac+	84	% Recov			

(Continued on next page)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130152

Description: RB-B4-01

Source: Well (Test/Observation)

Begin Date: 91/03/27 12:30

B/N/Acid Scan	Water-Total		B/N/Acid Scan	Water-Total		B/N/Acid Scan	Water-Total	
*** Continued	***		*** Continued	***		*** Continued	***	
Matrix Spike #1	Result	Units	Matrix Spike #1	Result	Units	Matrix Spike #2	Result	Units
Benzo(k)fluoranthene	0.03J*	ug/l	Benzo(ghi)perylene	68	% Recov	Anthracene	60	% Recov
Acenaphthylene	0.06UJ	ug/l	Indeno(1,2,3-cd)pyrene	72	% Recov	2,4-Dichlorophenol	76	% Recov
Chrysene	0.06UJ	ug/l	Benzo(b)fluoranthene	73	% Recov	Pyrene	83	% Recov
Retene	0.06UJ	ug/l	Fluoranthene	84	% Recov	Dibenzofuran	78	% Recov
4,6-Dinitro-2-methylph+	0.6UJ	ug/l	Benzo(k)fluoranthene	75	% Recov	Benzo(ghi)perylene	58	% Recov
Surrog: 2,4,6-Tribromo+	NAR	% Recov	Acenaphthylene	71	% Recov	Indeno(1,2,3-cd)pyrene	63	% Recov
Surrog: 2-Fluorobiphen+	37	% Recov	Chrysene	84	% Recov	Benzo(b)fluoranthene	64	% Recov
Surrog: 2-Fluorophenol	24	% Recov	Retene	NAR	% Recov	Fluoranthene	82	% Recov
Surrog: D14-Terphenyl	71	% Recov	4,6-Dinitro-2-methylph+	74	% Recov	Benzo(k)fluoranthene	67	% Recov
PYRENE-D10 (SS)	64	% Recov	Surrog: 2,4,6-Tribromo+	NAR	% Recov	Acenaphthylene	83	% Recov
Surrog: D5-Nitrobenzene	42	% Recov	Surrog: 2-Fluorobiphen+	57	% Recov	Chrysene	77	% Recov
Surrog: D5-Phenol	16	% Recov	Surrog: 2-Fluorophenol	38	% Recov	Retene	NAR	% Recov
			Surrog: D14-Terphenyl	71	% Recov	4,6-Dinitro-2-methylph+	83	% Recov
			PYRENE-D10 (SS)	80	% Recov	Surrog: 2,4,6-Tribromo+	NAR	% Recov
			Surrog: D5-Nitrobenzene	87	% Recov	Surrog: 2-Fluorobiphen+	75	% Recov
			Surrog: D5-Phenol	20	% Recov	Surrog: 2-Fluorophenol	40	% Recov
						Surrog: D14-Terphenyl	72	% Recov
						PYRENE-D10 (SS)	92	% Recov
						Surrog: D5-Nitrobenzene	100	% Recov
						Surrog: D5-Phenol	21	% Recov
B/N/Acid Scan	Water-Total		B/N/Acid Scan	Water-Total				
Matrix Spike #1	Result	Units	Matrix Spike #2	Result	Units			
Benzo(a)pyrene	74	% Recov	Benzo(a)pyrene	56	% Recov			
2,4-Dinitrophenol	98	% Recov	2,4-Dinitrophenol	94	% Recov			
Dibenzo(a,h)anthracene	61	% Recov	Dibenzo(a,h)anthracene	55	% Recov			
Benzo(a)anthracene	81	% Recov	Benzo(a)anthracene	77	% Recov			
4-Chloro-3-Methylphenol	73	% Recov	4-Chloro-3-Methylphenol	78	% Recov			
Acenaphthene	71	% Recov	Acenaphthene	84	% Recov			
Phenanthrene	79	% Recov	Phenanthrene	82	% Recov			
Fluorene	79	% Recov	Fluorene	88	% Recov			
Carbazole	NAR	% Recov	Carbazole	NAR	% Recov			
Pentachlorophenol	105	% Recov	Pentachlorophenol	106	% Recov			
2,4,6-Trichlorophenol	72	% Recov	2,4,6-Trichlorophenol	76	% Recov			
2-Nitrophenol	91	% Recov	2-Nitrophenol	95	% Recov			
Naphthalene, 1-Methyl-	NAR	% Recov	Naphthalene, 1-Methyl-	NAR	% Recov			
Naphthalene	67	% Recov	Naphthalene	82	% Recov			
2-Methylnaphthalene	38	% Recov	2-Methylnaphthalene	50	% Recov			
2-Chloronaphthalene	49	% Recov	2-Chloronaphthalene	64	% Recov			
2-Methylphenol	65	% Recov	2-Methylphenol	57	% Recov			
o-Chlorophenol	77	% Recov	o-Chlorophenol	76	% Recov			
2,4,5-Trichlorophenol	90	% Recov	2,4,5-Trichlorophenol	90	% Recov			
4-Nitrophenol	26	% Recov	4-Nitrophenol	20	% Recov			
2,4-Dimethylphenol	50	% Recov	2,4-Dimethylphenol	41	% Recov			
4-Methylphenol	49	% Recov	4-Methylphenol	38	% Recov			
Phenol	21	% Recov	Phenol	20	% Recov			
Anthracene	69	% Recov						
2,4-Dichlorophenol	74	% Recov						
Pyrene	83	% Recov						
Dibenzofuran	65	% Recov						

(Sample Complete)

17-JUL-91
11:41:40

EPA REGION 1 Lab Management System
Sample/Project Analysis Results

Page 0

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130153

Description: RB-B4-01

Source: Well (Test/Observation)

Begin Date: 91/03/27 12:30

Metals - Specified		Water-Filtere	
		Result	Units
Arsenic	As-Diss	1.5U	ug/l
Chromium	Cr-Diss	1.3B*	ug/l

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130154

Description: RB-B10-01

(Duplicate of B^{-H})^{B.F}

Source: Well (Test/Observation)

Begin Date: 91/03/27 12:45

Metals - Specified		Water-Total	
		Result	Units
Arsenic	As-Total	2.4J*	ug/l
Chromium	Cr-Total	14.5 *	ug/l
+-----+-----+-----+-----+			
VOA - PP Scan (GCMS)		Water-Total	
		Result	Units
+-----+-----+-----+-----+			
Carbon Tetrachloride		1U	ug/l
Acetone		1U	ug/l
Chloroform		1U	ug/l
Benzene		1U	ug/l
1,1,1-Trichloroethane		1U	ug/l
Bromomethane		1U	ug/l
Chloromethane		0.05J*	ug/l
Dibromomethane		1U	ug/l
Bromochloromethane		1U	ug/l
Chloroethane		1U	ug/l
Vinyl Chloride		1U	ug/l
Methylene Chloride		1U	ug/l
Carbon Disulfide		0.2J*	ug/l
Bromoform		1U	ug/l
Bromodichloromethane		1U	ug/l
1,1-Dichloroethane		1U	ug/l
1,1-Dichloroethene		1U	ug/l
Trichlorofluoromethane		1U	ug/l
Methane, Dichlorodiflu+		1U	ug/l
1,2-Dichloropropane		1U	ug/l
2-Butanone		1U	ug/l
1,1,2-Trichloroethane		1U	ug/l
Trichloroethene		1U	ug/l
ETHANE, 1,1,2,2-TETRAC+		1U	ug/l
1,2,3-Trichlorobenzene		1U	ug/l
Hexachlorobutadiene		1U	ug/l
Naphthalene		1U	ug/l
2-Chlorotoluene		1U	ug/l
1,2-Dichlorobenzene		1U	ug/l
1,2,4-Trimethylbenzene		1U	ug/l
1,2-Dibromo-3-chloropr+		1U	ug/l
1,2,3-Trichloropropane		1U	ug/l
Tert-Butylbenzene		1U	ug/l
Isopropylbenzene (Cume+		1U	ug/l
p-Isopropyltoluene		1U	ug/l
Ethylbenzene		1U	ug/l
BENZENE, ETHENYL-(STYR+		1U	ug/l
BENZENE, PROPYL-		1U	ug/l
+-----+-----+-----+-----+			
VOA - PP Scan (GCMS)		Water-Total	
		Result	Units
+-----+-----+-----+-----+			
Butylbenzene		1U	ug/l
4-Chlorotoluene		1U	ug/l
1,4-Dichlorobenzene		1U	ug/l
1,2-Dibromoethane (EDB)		1U	ug/l
1,2-Dichloroethane		0.2J*	ug/l
4-Methyl-2-Pentanone		1U	ug/l
1,3,5-Trimethylbenzene		1U	ug/l
Bromobenzene		1U	ug/l
Toluene		1U	ug/l
Chlorobenzene		1U	ug/l
1,2,4-Trichlorobenzene		1U	ug/l
Dibromochloromethane		1U	ug/l
Tetrachloroethene		1U	ug/l
Sec-Butylbenzene		1U	ug/l
1,3-Dichloropropane		1U	ug/l
Cis-1,2-Dichloroethene		1U	ug/l
trans-1,2-Dichloroethe+		1U	ug/l
1,3-Dichlorobenzene		1U	ug/l
1,1-Dichloropropene		1U	ug/l
2,2-Dichloropropane		1U	ug/l
2-Hexanone		1U	ug/l
Ethane, 1,1,1,2-Tetrac+		1U	ug/l
Total Xylenes		1U	ug/l
cis-1,3-Dichloropropene		1U	ug/l
trans-1,3-Dichloroprop+		1U	ug/l
p-Bromofluorobenzene		96	% Recov
Surrog: 1-Bromo-2-Fluo+		120	% Recov
d8-Toluene		100	% Recov
d4-1,2-Dichlorobenzene+		NAF	% Recov
1,2-Dichloroethane-d4 +		108	% Recov
+-----+-----+-----+-----+			
B/N/Acid Scan		Water-Total	
		Result	Units
+-----+-----+-----+-----+			
Benzo(a)pyrene		0.03J*	ug/l
2,4-Dinitrophenol		0.6UJ	ug/l
Dibenzo(a,h)anthracene		0.02J*	ug/l
Benzo(a)anthracene		0.06UJ	ug/l
4-Chloro-3-Methylphenol		0.06UJ	ug/l
Acenaphthene		0.0006J*	ug/l
Phenanthrene		0.007J*	ug/l
Fluorene		0.06UJ	ug/l
Carbazole		0.06UJ	ug/l
+-----+-----+-----+-----+			
B/N/Acid Scan		Water-Total	
		Result	Units
+-----+-----+-----+-----+			
Pentachlorophenol		0.02J*	ug/l
2,4,6-Trichlorophenol		0.06UJ	ug/l
2-Nitrophenol		0.06UJ	ug/l
Naphthalene, 1-Methyl-		0.003J*	ug/l
Naphthalene		0.06UJ	ug/l
2-Methylnaphthalene		0.003J*	ug/l
2-Chloronaphthalene		0.06UJ	ug/l
o-Methylphenol		0.06UJ	ug/l
o-Chlorophenol		0.06UJ	ug/l
2,4,5-Trichlorophenol		0.06UJ	ug/l
4-Nitrophenol		0.6UJ	ug/l
2,4-Dimethylphenol		0.06UJ	ug/l
4-Methylphenol		0.06UJ	ug/l
Phenol		0.07UJ	ug/l
Anthracene		0.06UJ	ug/l
2,4-Dichlorophenol		0.06UJ	ug/l
Pyrene		0.01J*	ug/l
Dibenzofuran		0.06UJ	ug/l
Benzo(ghi)perylene		0.06UJ	ug/l
Indeno(1,2,3-cd)pyrene		0.06UJ	ug/l
Benzo(b)fluoranthene		0.03J*	ug/l
Fluoranthene		0.008J*	ug/l
Benzo(k)fluoranthene		0.03J*	ug/l
Acenaphthylene		0.06UJ	ug/l
Chrysene		0.06UJ	ug/l
Retene		0.06UJ	ug/l
4,6-Dinitro-2-methylph+		0.6UJ	ug/l
Surrog: 2,4,6-Tribromo+		NAR	% Recov
Surrog: 2-Fluorobiphen+		46	% Recov
Surrog: 2-Fluorophenol		33	% Recov
Surrog: D14-Terphenyl		69	% Recov
PYRENE-D10 (SS)		62	% Recov
Surrog: D5-Nitrobenzene		50	% Recov
Surrog: D5-Phenol		21	% Recov

(Sample Complete)

11:41:40

Sample/Project Analysis Results

Page 5

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130155

Description: RB-B10-01 (Duplicate of B-4) BF

Source: Well (Test/Observation)

Begin Date: 91/03/27 12:45

Metals - Specified		Water-Filtere	
		Result	Units
Arsenic	As-Diss	1.5U	ug/l
Chromium	Cr-Diss	1.1B*	ug/l

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130156

Description: RB-B5-01

Source: Well (Test/Observation)

Begin Date: 91/03/27 15:00

+-----+ VOA - PP Scan (GCMS) +-----+			+-----+ VOA - PP Scan (GCMS) +-----+			+-----+ B/N/Acid Scan +-----+					
Water-Total		Units	Water-Total		Units	Water-Total		Units			
Result			Result			Result					
+-----+			+-----+			+-----+					
Carbon Tetrachloride	1U	ug/l	Bromobenzene	1U	ug/l	2-Methylphenol	0.1UJ	ug/l			
Acetone	1U	ug/l	Toluene	1U	ug/l	o-Chlorophenol	0.1UJ	ug/l			
Chloroform	0.1J*	ug/l	Chlorobenzene	1U	ug/l	2,4,5-Trichlorophenol	0.1UJ	ug/l			
Benzene	1U	ug/l	1,2,4-Trichlorobenzene	1U	ug/l	4-Nitrophenol	1UJ	ug/l			
1,1,1-Trichloroethane	1U	ug/l	Dibromochloromethane	1U	ug/l	2,4-Dimethylphenol	0.1UJ	ug/l			
Bromomethane	1U	ug/l	Tetrachloroethene	1U	ug/l	4-Methylphenol	0.1UJ	ug/l			
Chloromethane	0.1J*	ug/l	Sec-Butylbenzene	1U	ug/l	Phenol	0.1UJ	ug/l			
Dibromomethane	1U	ug/l	1,3-Dichloropropane	1U	ug/l	Anthracene	0.1UJ	ug/l			
Bromochloromethane	1U	ug/l	Cis-1,2-Dichloroethene	1U	ug/l	2,4-Dichlorophenol	0.1UJ	ug/l			
Chloroethane	1U	ug/l	trans-1,2-Dichloroethe+	1U	ug/l	Pyrene	0.02J*	ug/l			
Vinyl Chloride	1U	ug/l	1,3-Dichlorobenzene	1U	ug/l	Dibenzofuran	0.1UJ	ug/l			
Methylene Chloride	1U	ug/l	1,1-Dichloropropene	1U	ug/l	Benzo(ghi)perylene	0.1UJ	ug/l			
Carbon Disulfide	1U	ug/l	2,2-Dichloropropane	1U	ug/l	Indeno(1,2,3-cd)pyrene	0.1UJ	ug/l			
Bromoform	1U	ug/l	2-Hexanone	1U	ug/l	Benzo(b)fluoranthene	0.06J*	ug/l			
Bromodichloromethane	1U	ug/l	Ethane, 1,1,1,2-Tetrac+	1U	ug/l	Fluoranthene	0.02J*	ug/l			
1,1-Dichloroethane	1U	ug/l	Total Xylenes	1U	ug/l	Benzo(k)fluoranthene	0.03J*	ug/l			
1,1-Dichloroethene	1U	ug/l	cis-1,3-Dichloropropene	1U	ug/l	Acenaphthylene	0.1UJ	ug/l			
Trichlorofluoromethane	1U	ug/l	trans-1,3-Dichloroprop+	1U	ug/l	Chrysene	0.1UJ	ug/l			
Methane, Dichlorodiflu+	1U	ug/l	p-Bromofluorobenzene	101	% Recov	Retene	0.1UJ	ug/l			
1,2-Dichloropropane	1U	ug/l	Surrog: 1-Bromo-2-Fluo+	118	% Recov	4,6-Dinitro-2-methylph+	1UJ	ug/l			
2-Butanone	1.1U	ug/l	d8-Toluene	101	% Recov	Surrog: 2,4,6-Tribromo+	NAR	% Recov			
1,1,2-Trichloroethane	1U	ug/l	d4-1,2-Dichlorobenzene+	NAF	% Recov	Surrog: 2-Fluorobiphen+	49	% Recov			
Trichloroethene	1U	ug/l	1,2-Dichloroethane-d4 +	111	% Recov	Surrog: 2-Fluorophenol	42	% Recov			
ETHANE, 1,1,2,2-TETRAC+	1U	ug/l				Surrog: D14-Terphenyl	66	% Recov			
1,2,3-Trichlorobenzene	1U	ug/l				PYRENE-D10 (SS)	43	% Recov			
Hexachlorobutadiene	1U	ug/l				Surrog: D5-Nitrobenzene	51	% Recov			
Naphthalene	1U	ug/l				Surrog: D5-Phenol	31	% Recov			
2-Chlorotoluene	1U	ug/l									
1,2-Dichlorobenzene	1U	ug/l									
1,2,4-Trimethylbenzene	1U	ug/l									
1,2-Dibromo-3-chloropr+	1U	ug/l									
1,2,3-Trichloropropane	1U	ug/l									
Tert-Butylbenzene	1U	ug/l									
Isopropylbenzene (Cume+	1U	ug/l									
p-Isopropyltoluene	1U	ug/l									
Ethylbenzene	1U	ug/l									
BENZENE, ETHENYL-(STYR+	1U	ug/l									
BENZENE, PROPYL-	1U	ug/l									
Butylbenzene	1U	ug/l									
4-Chlorotoluene	1U	ug/l									
1,4-Dichlorobenzene	1U	ug/l									
1,2-Dibromoethane (EDB)	1U	ug/l									
1,2-Dichloroethane	0.5J*	ug/l									
4-Methyl-2-Pentanone	1U	ug/l									
1,3,5-Trimethylbenzene	1U	ug/l									

(Sample Complete)

Account: AGDD3A

Source: Well (Test/Observation)

(Sample Complete)

19-JUL-91

EPA Region X Lab Management System
Sample Procedure Analysis Units

Page 11

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130159

Description: RB-B6-01

Source: Well (Test/Observation)

Begin Date: 91/03/28 08:30

Metals - Specified		Water-Filtere	
		Result	Units
Arsenic	As-Diss	1.9J*	ug/l
Chromium	Cr-Diss	0.7JB*	ug/l

Metals - Specified		Water-Filtere	
Matrix Spike #1		Result	Units
Arsenic	As-Diss	100	% Recov

Metals - Specified		Water-Filtere	
Matrix Spike #2		Result	Units
Arsenic	As-Diss	102	% Recov

(Sample Complete)

11:41:40

Sample/Project Analysis Results

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130160

Description: RB-B20-01

(Trip blank)

Source: Well (Test/Observation)

Begin Date: 91/03/27 09:00

VOA - PP Scan (GCMS)			VOA - PP Scan (GCMS)		
Water-Total			Water-Total		
Result Units			Result Units		
			*** Continued ***		
Carbon Tetrachloride	1U	ug/l	Bromobenzene	1U	ug/l
Acetone	1U	ug/l	Toluene	1U	ug/l
Chloroform	0.04J*	ug/l	Chlorobenzene	1U	ug/l
Benzene	1U	ug/l	1,2,4-Trichlorobenzene	1U	ug/l
1,1,1-Trichloroethane	1U	ug/l	Dibromochloromethane	1U	ug/l
Bromomethane	1U	ug/l	Tetrachloroethene	1U	ug/l
Chloromethane	1U	ug/l	Sec-Butylbenzene	1U	ug/l
Dibromomethane	1U	ug/l	1,3-Dichloropropane	1U	ug/l
Bromochloromethane	1U	ug/l	Cis-1,2-Dichloroethene	1U	ug/l
Chloroethane	1U	ug/l	trans-1,2-Dichloroethe+	1U	ug/l
Vinyl Chloride	1U	ug/l	1,3-Dichlorobenzene	1U	ug/l
Methylene Chloride	1U	ug/l	1,1-Dichloropropene	1U	ug/l
Carbon Disulfide	1U	ug/l	2,2-Dichloropropane	1U	ug/l
Bromoform	1U	ug/l	2-Hexanone	1U	ug/l
Bromodichloromethane	1U	ug/l	Ethane, 1,1,1,2-Tetrac+	1U	ug/l
1,1-Dichloroethane	1U	ug/l	Total Xylenes	1U	ug/l
1,1-Dichloroethene	1U	ug/l	cis-1,3-Dichloropropene	1U	ug/l
Trichlorofluoromethane	1U	ug/l	trans-1,3-Dichloroprop+	1U	ug/l
Methane, Dichlorodiflu+	1U	ug/l	p-Bromofluorobenzene	100	% Recov
1,2-Dichloropropane	1U	ug/l	Surrog: 1-Bromo-2-Fluo+	89	% Recov
2-Butanone	1U	ug/l	d8-Toluene	91	% Recov
1,1,2-Trichloroethane	1U	ug/l	d4-1,2-Dichlorobenzene+	NAF	% Recov
Trichloroethene	1U	ug/l	1,2-Dichloroethane-d4 +	95	% Recov
ETHANE, 1,1,2,2-TETRAC+	1U	ug/l			
1,2,3-Trichlorobenzene	1U	ug/l			
Hexachlorobutadiene	1U	ug/l			
Naphthalene	1U	ug/l			
2-Chlorotoluene	1U	ug/l			
1,2-Dichlorobenzene	1U	ug/l			
1,2,4-Trimethylbenzene	1U	ug/l			
1,2-Dibromo-3-chloropr+	1U	ug/l			
1,2,3-Trichloropropane	1U	ug/l			
Tert-Butylbenzene	1U	ug/l			
Isopropylbenzene (Cume+	1U	ug/l			
p-Isopropyltoluene	1U	ug/l			
Ethylbenzene	1U	ug/l			
BENZENE, ETHENYL-(STYR+	1U	ug/l			
BENZENE, PROPYL-	1U	ug/l			
Butylbenzene	1U	ug/l			
4-Chlorotoluene	1U	ug/l			
1,4-Dichlorobenzene	1U	ug/l			
1,2-Dibromoethane (EDB)	1U	ug/l			
1,2-Dichloroethane	1U	ug/l			
4-Methyl-2-Pentanone	1U	ug/l			
1,3,5-Trimethylbenzene	1U	ug/l			

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130161

Description: RB-B25-01

(Ambient condition / Field (transfer) blank)

Source: Well (Test/Observation)

Begin Date: 91/03/28 12:00

VOA - PP Scan (GCMS)		Water-Total		VOA - PP Scan (GCMS)		Water-Total	
		Result	Units	*** Continued ***		Result	Units
Carbon Tetrachloride	1U	ug/l		Bromobenzene	1U	ug/l	
Acetone	1U	ug/l		Toluene	1U	ug/l	
Chloroform	4.6 *	ug/l		Chlorobenzene	1U	ug/l	
Benzene	1U	ug/l		1,2,4-Trichlorobenzene	1U	ug/l	
1,1,1-Trichloroethane	1U	ug/l		Dibromochloromethane	0.08J*	ug/l	
Bromomethane	1U	ug/l		Tetrachloroethene	1U	ug/l	
Chloromethane	1U	ug/l		Sec-Butylbenzene	1U	ug/l	
Dibromomethane	1U	ug/l		1,3-Dichloropropane	1U	ug/l	
Bromochloromethane	1U	ug/l		Cis-1,2-Dichloroethene	1U	ug/l	
Chloroethane	1U	ug/l		trans-1,2-Dichloroethe+	1U	ug/l	
Vinyl Chloride	1U	ug/l		1,3-Dichlorobenzene	1U	ug/l	
Methylene Chloride	1U	ug/l		1,1-Dichloropropene	1U	ug/l	
Carbon Disulfide	1U	ug/l		2,2-Dichloropropane	1U	ug/l	
Bromoform	1U	ug/l		2-Hexanone	1U	ug/l	
Bromodichloromethane	1U	ug/l		Ethane, 1,1,1,2-Tetrac+	1U	ug/l	
1,1-Dichloroethane	1U	ug/l		Total Xylenes	1U	ug/l	
1,1-Dichloroethene	1U	ug/l		cis-1,3-Dichloropropene	1U	ug/l	
Trichlorofluoromethane	1U	ug/l		trans-1,3-Dichloroprop+	1U	ug/l	
Methane, Dichlorodiflu+	1U	ug/l		p-Bromofluorobenzene	90	% Recov	
1,2-Dichloropropane	1U	ug/l		Surrog: 1-Bromo-2-Fluo+	97	% Recov	
2-Butanone	1U	ug/l		d8-Toluene	90	% Recov	
1,1,2-Trichloroethane	1U	ug/l		d4-1,2-Dichlorobenzene+	NAF	% Recov	
Trichloroethene	1U	ug/l		1,2-Dichloroethane-d4 +	88	% Recov	
ETHANE, 1,1,2,2-TETRAC+	1U	ug/l					
1,2,3-Trichlorobenzene	1U	ug/l					
Hexachlorobutadiene	1U	ug/l					
Naphthalene	1U	ug/l					
2-Chlorotoluene	1U	ug/l					
1,2-Dichlorobenzene	1U	ug/l					
1,2,4-Trimethylbenzene	1U	ug/l					
1,2-Dibromo-3-chloropr+	1U	ug/l					
1,2,3-Trichloropropane	1U	ug/l					
Tert-Butylbenzene	1U	ug/l					
Isopropylbenzene (Cume+	1U	ug/l					
p-Isopropyltoluene	1U	ug/l					
Ethylbenzene	1U	ug/l					
BENZENE, ETHENYL-(STYR+	1U	ug/l					
BENZENE, PROPYL-	1U	ug/l					
Butylbenzene	1U	ug/l					
4-Chlorotoluene	1U	ug/l					
1,4-Dichlorobenzene	1U	ug/l					
1,2-Dibromoethane (EDB)	1U	ug/l					
1,2-Dichloroethane	1U	ug/l					
4-Methyl-2-Pentanone	1U	ug/l					
1,3,5-Trimethylbenzene	1U	ug/l					

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130162

Description: RB-TD1-01

(Tox Drain 1)

Source: Well (Test/Observation)

Begin Date: 91/03/28 09:45

from water standing in toe drain

Metals - Specified			Water-Total		VOA - PP Scan (GCMS)			Water-Total		B/N/Acid Scan			Water-Total	
			Result	Units	*** Continued ***			Result	Units	*** Continued ***			Result	Units
Arsenic	As-Total	1.5U	ug/l											
Chromium	Cr-Total	1.1B*	ug/l											
+-----														

(Sample Complete)

19-JUL-91
11:41:00

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130163

Description: RB-TD1-01

Source: Well (Test/Observation)

Begin Date: 91/03/28 10:00

Metals - Specified		Water-Filtere	
		Result	Units
Arsenic	As-Diss	1.5U	ug/l
Chromium	Cr-Diss	0.4JB*	ug/l

(Sample Complete)

11:41:40

Sample/Project Analysis Results

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130164

Description: RB-TD2-01

(Tox Anal 2)
from inlet

Source: Well (Test/Observation)

Begin Date: 91/03/28 10:40

Metals - Specified			Water-Total		VOA - PP Scan (GCMS)			Water-Total		B/N/Acid Scan			Water-Total	
			Result	Units	*** Continued ***			Result	Units	*** Continued ***			Result	Units
Arsenic	As-Total	1.5U	ug/l											
Chromium	Cr-Total	1.9 *	ug/l											

11:41:40

Sample/Project Analysis Results

Page 11

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130165

Description: RB-TD2-01

Source: Well (Test/Observation)

Begin Date: 91/03/28 11:05

Metals - Specified		Water-Filtere	
		Result	Units
Arsenic	As-Diss	1.5U	ug/l
Chromium	Cr-Diss	0.9JB*	ug/l

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130166

Description: RB-TD10-01 (Duplicate of TD-1)

Source: Well (Test/Observation)

Begin Date: 91/03/28 09:55

Metals - Specified				Water-Total		VOA - PP Scan (GCMS)				Water-Total		B/N/Acid Scan				Water-Total	
				Result	Units	*** Continued				Result	Units	*** Continued				Result	Units
Arsenic As-Total				1.5U	ug/l												
Chromium Cr-Total				1.4B*	ug/l												
VOA - PP Scan (GCMS)				Water-Total													
				Result	Units												
Carbon Tetrachloride				1U	ug/l	Butylbenzene				1U	ug/l	Pentachlorophenol				1J*	ug/l
Acetone				1U	ug/l	4-Chlorotoluene				1U	ug/l	2,4,6-Trichlorophenol				0.06UJ	ug/l
Chloroform				1U	ug/l	1,4-Dichlorobenzene				1U	ug/l	2-Nitrophenol				0.06UJ	ug/l
Benzene				1U	ug/l	1,2-Dibromoethane (EDB)				1U	ug/l	Naphthalene, 1-Methyl-				0.1J*	ug/l
1,1,1-Trichloroethane				1U	ug/l	1,2-Dichloroethane				0.4J*	ug/l	Naphthalene				0.4J*	ug/l
Bromomethane				1U	ug/l	4-Methyl-2-Pentanone				1U	ug/l	2-Methylnaphthalene				0.01J*	ug/l
Chloromethane				1U	ug/l	1,3,5-Trimethylbenzene				1U	ug/l	2-Chloronaphthalene				0.06UJ	ug/l
Dibromomethane				1U	ug/l	Bromobenzene				1U	ug/l	2-Methylphenol				0.002J*	ug/l
Bromochloromethane				1U	ug/l	Toluene				1U	ug/l	o-Chlorophenol				0.06UJ	ug/l
Chloroethane				0.1J*	ug/l	Chlorobenzene				1U	ug/l	2,4,5-Trichlorophenol				0.06UJ	ug/l
Vinyl Chloride				1U	ug/l	1,2,4-Trichlorobenzene				1U	ug/l	4-Nitrophenol				0.6UJ	ug/l
Methylene Chloride				1U	ug/l	Dibromochloromethane				1U	ug/l	2,4-Dimethylphenol				0.06UJ	ug/l
Carbon Disulfide				1U	ug/l	Tetrachloroethene				1U	ug/l	4-Methylphenol				0.006J*	ug/l
Bromoform				1U	ug/l	Sec-Butylbenzene				1U	ug/l	Phenol				0.06UJ	ug/l
Bromodichloromethane				1U	ug/l	1,3-Dichloropropane				1U	ug/l	Anthracene				0.04J*	ug/l
1,1-Dichloroethane				1U	ug/l	Cis-1,2-Dichloroethene				1U	ug/l	2,4-Dichlorophenol				0.06UJ	ug/l
1,1-Dichloroethene				1U	ug/l	trans-1,2-Dichloroethene				1U	ug/l	Pyrene				0.09J*	ug/l
Trichlorofluoromethane				1U	ug/l	1,3-Dichlorobenzene				1U	ug/l	Dibenzofuran				0.2J*	ug/l
Methane, Dichlorodifluoride				1U	ug/l	1,1-Dichloropropene				1U	ug/l	Benzo(ghi)perylene				0.06UJ	ug/l
1,2-Dichloropropane				1U	ug/l	2,2-Dichloropropane				1U	ug/l	Indeno(1,2,3-cd)pyrene				0.06UJ	ug/l
2-Butanone				1U	ug/l	2-Hexanone				1U	ug/l	Benzo(b)fluoranthene				0.06UJ	ug/l
1,1,2-Trichloroethane				1U	ug/l	Ethane, 1,1,1,2-Tetrachloride				1U	ug/l	Fluoranthene				0.08J*	ug/l
Trichloroethene				1U	ug/l	Total Xylenes				1U	ug/l	Benzo(k)fluoranthene				0.06UJ	ug/l
ETHANE, 1,1,2,2-TETRACHLORIDE				1U	ug/l	Cis-1,3-Dichloropropene				1U	ug/l	Acenaphthylene				0.01J*	ug/l
1,2,3-Trichlorobenzene				1U	ug/l	trans-1,3-Dichloropropene				1U	ug/l	Chrysene				0.06UJ	ug/l
Hexachlorobutadiene				1U	ug/l	p-Bromofluorobenzene				94	% Recov	Retene				0.06UJ	ug/l
Naphthalene				1U	ug/l	Surrog: 1-Bromo-2-Fluorobenzene				107	% Recov	4,6-Dinitro-2-methylphenol				0.6UJ	ug/l
2-Chlorotoluene				1U	ug/l	d8-Toluene				91	% Recov	Surrog: 2,4,6-Tribromophenol				NAR	% Recov
1,2-Dichlorobenzene				1U	ug/l	d4-1,2-Dichlorobenzene+d8-1,2-Dichloroethane-d4				NAF	% Recov	Surrog: 2-Fluorobiphenyl				52	% Recov
1,2,4-Trimethylbenzene				1U	ug/l					96	% Recov	Surrog: 2-Fluorophenol				37	% Recov
1,2-Dibromo-3-chloropropane				1U	ug/l							Surrog: D14-Terphenyl				85	% Recov
1,2,3-Trichloropropane				1U	ug/l							PYRENE-D10 (SS)				88	% Recov
Tert-Butylbenzene				1U	ug/l							Surrog: D5-Nitrobenzene				57	% Recov
Isopropylbenzene (Cumene)				1U	ug/l							Surrog: D5-Phenol				22	% Recov
p-Isopropyltoluene				1U	ug/l												
Ethylbenzene				1U	ug/l												
BENZENE, ETHENYL-(STYRENE)				1U	ug/l												
BENZENE, PROPYL-				1U	ug/l												

EPA Region X Lab Management System
Sa / Pro Ar is lts

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130167

Description: RB-TD10-01

(Duplicate of TD-1)

Source: Well (Test/Observation)

Begin Date: 91/03/28 10:20

Metals - Specified		Water-Filtere	Result Units
Arsenic	As-Diss	1.5U	ug/l
Chromium	Cr-Diss	0.3JB*	ug/l

(Sample Complete)

11:41:40

Sample/Project Analysis Results

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130168

Description: RB-TD15-01 (Equipment Rinse Blank)

Source: Well (Test/Observation)

Begin Date: 91/03/28 11:25

Metals - Specified			VOA - PP Scan (GCMS)			B/N/Acid Scan		
		Water-Total			Water-Total			Water-Total
		Result Units	*** Continued ***		Result Units	*** Continued ***		Result Units
Arsenic	As-Total	1.5U ug/l						
Chromium	Cr-Total	1.5B* ug/l						
			Butylbenzene	1U ug/l	Pentachlorophenol	0.6UJ ug/l		
			4-Chlorotoluene	1U ug/l	2,4,6-Trichlorophenol	0.06UJ ug/l		
			1,4-Dichlorobenzene	1U ug/l	2-Nitrophenol	0.06UJ ug/l		
			1,2-Dibromoethane (EDB)	1U ug/l	Naphthalene, 1-Methyl-	0.06UJ ug/l		
			1,2-Dichloroethane	0.6J* ug/l	Naphthalene	0.06UJ ug/l		
			4-Methyl-2-Pentanone	1U ug/l	2-Methylnaphthalene	0.06UJ ug/l		
			1,3,5-Trimethylbenzene	1U ug/l	2-Chloronaphthalene	0.06UJ ug/l		
			Bromobenzene	1U ug/l	2-Methylphenol	0.06UJ ug/l		
			Toluene	0.5J* ug/l	o-Chlorophenol	0.06UJ ug/l		
			Chlorobenzene	1U ug/l	2,4,5-Trichlorophenol	0.06UJ ug/l		
			1,2,4-Trichlorobenzene	1U ug/l	4-Nitrophenol	0.6UJ ug/l		
			Dibromochloromethane	1U ug/l	2,4-Dimethylphenol	0.06UJ ug/l		
			Tetrachloroethene	1U ug/l	4-Methylphenol	0.06UJ ug/l		
			Sec-Butylbenzene	1U ug/l	Phenol	0.1UJ ug/l		
			1,3-Dichloropropane	1U ug/l	Anthracene	0.06UJ ug/l		
			Cis-1,2-Dichloroethene	1U ug/l	2,4-Dichlorophenol	0.06UJ ug/l		
			trans-1,2-Dichloroethe+	1U ug/l	Pyrene	0.06UJ ug/l		
			1,3-Dichlorobenzene	1U ug/l	Dibenzofuran	0.06UJ ug/l		
			1,1-Dichloropropene	1U ug/l	Benzo(ghi)perylene	0.06UJ ug/l		
			2,2-Dichloropropane	1U ug/l	Indeno(1,2,3-cd)pyrene	0.06UJ ug/l		
			2-Hexanone	1U ug/l	Benzo(b)fluoranthene	0.06UJ ug/l		
			Ethane, 1,1,1,2-Tetrac+	1U ug/l	Fluoranthene	0.06UJ ug/l		
			Total Xylenes	1U ug/l	Benzo(k)fluoranthene	0.06UJ ug/l		
			cis-1,3-Dichloropropene	1U ug/l	Acenaphthylene	0.06UJ ug/l		
			trans-1,3-Dichloroprop+	1U ug/l	Chrysene	0.06UJ ug/l		
			p-Bromofluorobenzene	93 % Recov	Retene	0.06UJ ug/l		
			Surrog: 1-Bromo-2-Fluo+	108 % Recov	4,6-Dinitro-2-methylph+	0.6UJ ug/l		
			d8-Toluene	93 % Recov	Surrog: 2,4,6-Trihromo+	NAR % Recov		
			d4-1,2-Dichlorobenzene+	NAF % Recov	Surrog: 2-Fluorobiphen+	57 % Recov		
			1,2-Dichloroethane-d4 +	96 % Recov	Surrog: 2-Fluorophenol	36 % Recov		
					Surrog: D14-Terphenyl	81 % Recov		
					PYRENE-D10 (SS)	82 % Recov		
					Surrog: D5-Nitrobenzene	58 % Recov		
					Surrog: D5-Phenol	20 % Recov		
			Benzo(a)pyrene	0.06UJ ug/l				
			2,4-Dinitrophenol	0.6UJ ug/l				
			Dibenzo(a,h)anthracene	0.06UJ ug/l				
			Benzo(a)anthracene	0.06UJ ug/l				
			4-Chloro-3-Methylphenol	0.06UJ ug/l				
			Acenaphthene	0.06UJ ug/l				
			Phenanthrene	0.06UJ ug/l				
			Fluorene	0.06UJ ug/l				
			Carbazole	0.06UJ ug/l				

17-000-71
41:70

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Laboratory: EPA, Manchester

Sample No: 91 130169

Description: RB-TD15-01 (Equipment Rinse Blank)

Source: Well (Test/Observation)

Begin Date: 91/03/28 11:40

+-----+-----+-----+		
Metals - Specified	Water-Filtere	
	Result	Units
+-----+-----+-----+		
Arsenic As-Diss	1.5U	ug/l
Chromium Cr-Diss	1.3JB*	ug/l

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Blank ID: BW1093

B/N/Acid Scan	Water-Total	
Blank #1	Result	Units
Benzo(a)pyrene	0.07UJ	ug/l
2,4-Dinitrophenol	0.7UJ	ug/l
Dibenzo(a,h)anthracene	0.07UJ	ug/l
Benzo(a)anthracene	0.07UJ	ug/l
4-Chloro-3-Methylphenol	0.07UJ	ug/l
Acenaphthene	0.07UJ	ug/l
Phenanthrene	0.07UJ	ug/l
Fluorene	0.07UJ	ug/l
Carbazole	0.07UJ	ug/l
Pentachlorophenol	0.7UJ	ug/l
2,4,6-Trichlorophenol	0.07UJ	ug/l
2-Nitrophenol	0.07UJ	ug/l
Naphthalene, 1-Methyl-	0.07UJ	ug/l
Naphthalene	0.005J*	ug/l
2-Methylnaphthalene	0.07UJ	ug/l
2-Chloronaphthalene	0.07UJ	ug/l
2-Methylphenol	0.07UJ	ug/l
o-Chlorophenol	0.07UJ	ug/l
2,4,5-Trichlorophenol	0.07UJ	ug/l
4-Nitrophenol	0.7UJ	ug/l
2,4-Dimethylphenol	0.07UJ	ug/l
4-Methylphenol	0.07UJ	ug/l
Phenol	0.06J*	ug/l
Anthracene	0.07UJ	ug/l
2,4-Dichlorophenol	0.07UJ	ug/l
Pyrene	0.07UJ	ug/l
Dibenzofuran	0.07UJ	ug/l
Benzo(ghi)perylene	0.07UJ	ug/l
Indeno(1,2,3-cd)pyrene	0.07UJ	ug/l
Benzo(b)fluoranthene	0.07UJ	ug/l
Fluoranthene	0.07UJ	ug/l
Benzo(k)fluoranthene	0.07UJ	ug/l
Acenaphthylene	0.07UJ	ug/l
Chrysene	0.07UJ	ug/l
Retene	0.07UJ	ug/l
4,6-Dinitro-2-methylph+	0.7UJ	ug/l
Surrog: 2,4,6-Tribromo+	NAR	% Recov
Surrog: 2-Fluorobiphen+	54	% Recov
Surrog: 2-Fluorophenol	47	% Recov
Surrog: D14-Terphenyl	98	% Recov
PYRENE-D10 (SS)	100	% Recov
Surrog: D5-Nitrobenzene	60	% Recov
Surrog: D5-Phenol	31	% Recov

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Blank ID: BW1093D

+-----+-----+-----+		
B/N/Acid Scan	Water-Total	
Blank #2	Result	Units
+-----+-----+-----+		
Benzo(a)pyrene	0.07UJ	ug/l
2,4-Dinitrophenol	0.7UJ	ug/l
Dibenzo(a,h)anthracene	0.07UJ	ug/l
Benzo(a)anthracene	0.07UJ	ug/l
4-Chloro-3-Methylphenol	0.07UJ	ug/l
Acenaphthene	0.07UJ	ug/l
Phenanthrene	0.07UJ	ug/l
Fluorene	0.07UJ	ug/l
Carbazole	0.07UJ	ug/l
Pentachlorophenol	0.7UJ	ug/l
2,4,6-Trichlorophenol	0.07UJ	ug/l
2-Nitrophenol	0.07UJ	ug/l
Naphthalene, 1-Methyl-	0.07UJ	ug/l
Naphthalene	0.004J*	ug/l
2-Methylnaphthalene	0.07UJ	ug/l
2-Chloronaphthalene	0.07UJ	ug/l
2-Methylphenol	0.07UJ	ug/l
o-Chlorophenol	0.07UJ	ug/l
2,4,5-Trichlorophenol	0.07UJ	ug/l
4-Nitrophenol	0.7UJ	ug/l
2,4-Dimethylphenol	0.07UJ	ug/l
4-Methylphenol	0.07UJ	ug/l
Phenol	0.05J*	ug/l
Anthracene	0.07UJ	ug/l
2,4-Dichlorophenol	0.07UJ	ug/l
Pyrene	0.07UJ	ug/l
Dibenzofuran	0.07UJ	ug/l
Benzo(ghi)perylene	0.07UJ	ug/l
Indeno(1,2,3-cd)pyrene	0.07UJ	ug/l
Benzo(b)fluoranthene	0.07UJ	ug/l
Fluoranthene	0.07UJ	ug/l
Benzo(k)fluoranthene	0.07UJ	ug/l
Acenaphthylene	0.07UJ	ug/l
Chrysene	0.07UJ	ug/l
Retene	0.07UJ	ug/l
4,6-Dinitro-2-methylph	0.7UJ	ug/l
Surrog: 2,4,6-Tribromo+	NAR	% Recov
Surrog: 2-Fluorobiphen+	49	% Recov
Surrog: 2-Fluorophenol	42	% Recov
Surrog: D14-Terphenyl	88	% Recov
PYRENE-D10 (SS)	90	% Recov
Surrog: D5-Nitrobenzene	58	% Recov
Surrog: D5-Phenol	28	% Recov

(Sample Complete)

11:41:40

Sample/Project Analysis Results

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Blank ID: BW1099

VOA - PP Scan (GCMS)			VOA - PP Scan (GCMS)		
Blank #1			*** Continued ***		
	Water-Total			Water-Total	
	Result	Units	Blank #1	Result	Units
Carbon Tetrachloride	1U	ug/l	Bromobenzene	1U	ug/l
Acetone	4.8 *	ug/l	Toluene	1U	ug/l
Chloroform	1U	ug/l	Chlorobenzene	1U	ug/l
Benzene	0.03J*	ug/l	1,2,4-Trichlorobenzene	0.06J*	ug/l
1,1,1-Trichloroethane	1U	ug/l	Dibromochloromethane	1U	ug/l
Bromomethane	1U	ug/l	Tetrachloroethene	1U	ug/l
Chloromethane	1U	ug/l	Sec-Butylbenzene	1U	ug/l
Dibromomethane	1U	ug/l	1,3-Dichloropropane	1U	ug/l
Bromochloromethane	1U	ug/l	Cis-1,2-Dichloroethene	1U	ug/l
Chloroethane	1U	ug/l	trans-1,2-Dichloroethe+	1U	ug/l
Vinyl Chloride	1U	ug/l	1,3-Dichlorobenzene	0.03J*	ug/l
Methylene Chloride	0.7J*	ug/l	1,1-Dichloropropene	1U	ug/l
Carbon Disulfide	1U	ug/l	2,2-Dichloropropane	1U	ug/l
Bromoform	1U	ug/l	2-Hexanone	1U	ug/l
Bromodichloromethane	1U	ug/l	Ethane, 1,1,1,2-Tetrac+	1U	ug/l
1,1-Dichloroethane	1U	ug/l	Total Xylenes	0.02J*	ug/l
1,1-Dichloroethene	1U	ug/l	cis-1,3-Dichloropropene	1U	ug/l
Trichlorofluoromethane	1U	ug/l	trans-1,3-Dichloroprop+	1U	ug/l
Methane, Dichlorodiflu+	1U	ug/l	p-Bromofluorobenzene	101	% Recov
1,2-Dichloropropane	1U	ug/l	Surrog: 1-Bromo-2-Fluo+	92	% Recov
2-Butanone	0.6J*	ug/l	d8-Toluene	96	% Recov
1,1,2-Trichloroethane	1U	ug/l	d4-1,2-Dichlorobenzene+	NAF	% Recov
Trichloroethene	1U	ug/l	1,2-Dichloroethane-d4 +	97	% Recov
ETHANE, 1,1,2,2-TETRAC+	1U	ug/l			
1,2,3-Trichlorobenzene	0.07J*	ug/l			
Hexachlorobutadiene	1U	ug/l			
Naphthalene	1U	ug/l			
2-Chlorotoluene	1U	ug/l			
1,2-Dichlorobenzene	1U	ug/l			
1,2,4-Trimethylbenzene	1U	ug/l			
1,2-Dibromo-3-chloropr+	1U	ug/l			
1,2,3-Trichloropropane	1U	ug/l			
Tert-Butylbenzene	1U	ug/l			
Isopropylbenzene (Cume+	1U	ug/l			
p-Isopropyltoluene	1U	ug/l			
Ethylbenzene	1U	ug/l			
BENZENE, ETHENYL-(STYR+	1U	ug/l			
BENZENE, PROPYL-	1U	ug/l			
Butylbenzene	1U	ug/l			
4-Chlorotoluene	1U	ug/l			
1,4-Dichlorobenzene	1U	ug/l			
1,2-Dibromoethane (EDB)	1U	ug/l			
1,2-Dichloroethane	1U	ug/l			
4-Methyl-2-Pentanone	1U	ug/l			
1,3,5-Trimethylbenzene	1U	ug/l			

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Blank ID: BW1100

VOA - PP Scan (GCMS)			VOA - PP Scan (GCMS)		
Blank #2			*** Continued ***		
	Water-Total			Water-Total	
	Result	Units	Blank #2	Result	Units
Carbon Tetrachloride	1U	ug/l	Bromobenzene	1U	ug/l
Acetone	3.8 *	ug/l	Toluene	0.02J*	ug/l
Chloroform	1U	ug/l	Chlorobenzene	1U	ug/l
Benzene	1U	ug/l	1,2,4-Trichlorobenzene	0.05J*	ug/l
1,1,1-Trichloroethane	1U	ug/l	Dibromochloromethane	1U	ug/l
Bromomethane	1U	ug/l	Tetrachloroethene	1U	ug/l
Chloromethane	1U	ug/l	Sec-Butylbenzene	0.01J*	ug/l
Dibromomethane	1U	ug/l	1,3-Dichloropropane	1U	ug/l
Bromochloromethane	1U	ug/l	Cis-1,2-Dichloroethene	1U	ug/l
Chloroethane	1U	ug/l	trans-1,2-Dichloroethe+	1U	ug/l
Vinyl Chloride	1U	ug/l	1,3-Dichlorobenzene	0.03J*	ug/l
Methylene Chloride	5.6 *	ug/l	1,1-Dichloropropene	1U	ug/l
Carbon Disulfide	0.1J*	ug/l	2,2-Dichloropropane	1U	ug/l
Bromoform	1U	ug/l	2-Hexanone	1U	ug/l
Bromodichloromethane	1U	ug/l	Ethane, 1,1,1,2-Tetrac+	1U	ug/l
1,1-Dichloroethane	1U	ug/l	Total Xylenes	1U	ug/l
1,1-Dichloroethene	1U	ug/l	cis-1,3-Dichloropropene	1U	ug/l
Trichlorofluoromethane	1U	ug/l	trans-1,3-Dichloroprop+	1U	ug/l
Methane, Dichlorodiflu+	1U	ug/l	p-Bromofluorobenzene	92	% Recov
1,2-Dichloropropane	1U	ug/l	Surrog: 1-Bromo-2-Fluo+	104	% Recov
2-Butanone	0.9J*	ug/l	d8-Toluene	91	% Recov
1,1,2-Trichloroethane	1U	ug/l	d4-1,2-Dichlorobenzene+	NAF	% Recov
Trichloroethene	1U	ug/l	1,2-Dichloroethane-d4 +	98	% Recov
ETHANE, 1,1,2,2-TETRAC+	1U	ug/l			
1,2,3-Trichlorobenzene	0.07J*	ug/l			
Hexachlorobutadiene	1U	ug/l			
Naphthalene	1U	ug/l			
2-Chlorotoluene	1U	ug/l			
1,2-Dichlorobenzene	0.04J*	ug/l			
1,2,4-Trimethylbenzene	0.02J*	ug/l			
1,2-Dibromo-3-chloropr+	1U	ug/l			
1,2,3-Trichloropropane	1U	ug/l			
Tert-Butylbenzene	1U	ug/l			
Isopropylbenzene (Cume+	1U	ug/l			
p-Isopropyltoluene	1U	ug/l			
Ethylbenzene	1U	ug/l			
BENZENE, ETHENYL-(STYR+	1U	ug/l			
BENZENE, PROPYL-	1U	ug/l			
Butylbenzene	0.02J*	ug/l			
4-Chlorotoluene	1U	ug/l			
1,4-Dichlorobenzene	1U	ug/l			
1,2-Dibromoethane (EDB)	1U	ug/l			
1,2-Dichloroethane	1U	ug/l			
4-Methyl-2-Pentanone	1U	ug/l			
1,3,5-Trimethylbenzene	0.01J*	ug/l			

(Sample Complete)

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Blank ID: BW1101

+-----+ VOA - PP Scan (GCMS) Water-Total Blank #3 Result Units +-----+			+-----+ VOA - PP Scan (GCMS) Water-Total *** Continued *** Result Units +-----+		
Carbon Tetrachloride	0.5U	ug/l	Bromobenzene	0.5U	ug/l
Acetone	8 *	ug/l	Toluene	0.5U	ug/l
Chloroform	0.5U	ug/l	Chlorobenzene	0.5U	ug/l
Benzene	0.5U	ug/l	1,2,4-Trichlorobenzene	0.3J*	ug/l
1,1,1-Trichloroethane	0.5U	ug/l	Dibromochloromethane	0.5U	ug/l
Bromomethane	0.5U	ug/l	Tetrachloroethene	0.5U	ug/l
Chloromethane	0.5U	ug/l	Sec-Butylbenzene	0.5U	ug/l
Dibromomethane	0.5U	ug/l	1,3-Dichloropropane	0.5U	ug/l
Bromochloromethane	0.5U	ug/l	Cis-1,2-Dichloroethene	0.5U	ug/l
Chloroethane	0.5U	ug/l	trans-1,2-Dichloroethe+	0.5U	ug/l
Vinyl Chloride	0.5U	ug/l	1,3-Dichlorobenzene	0.5U	ug/l
Methylene Chloride	2 *	ug/l	1,1-Dichloropropene	0.5U	ug/l
Carbon Disulfide	0.5U	ug/l	2,2-Dichloropropane	0.5U	ug/l
Bromoform	0.5U	ug/l	2-Hexanone	0.5U	ug/l
Bromodichloromethane	0.5U	ug/l	Ethane, 1,1,1,2-Tetrac+	0.5U	ug/l
1,1-Dichloroethane	0.5U	ug/l	Total Xylenes	0.5U	ug/l
1,1-Dichloroethene	0.5U	ug/l	cis-1,3-Dichloropropene	0.5U	ug/l
Trichlorofluoromethane	0.5U	ug/l	trans-1,3-Dichloroprop+	0.5U	ug/l
Methane, Dichlorodiflu+	0.5U	ug/l	p-Bromofluorobenzene	98	% Recov
1,2-Dichloropropane	0.5U	ug/l	Surrog: 1-Bromo-2-Fluo+	91	% Recov
2-Butanone	4 *	ug/l	d8-Toluene	94	% Recov
1,1,2-Trichloroethane	0.5U	ug/l	d4-1,2-Dichlorobenzene+	NAF	% Recov
Trichloroethene	0.5U	ug/l	1,2-Dichloroethane-d4 +	98	% Recov
ETHANE, 1,1,2,2-TETRAC+	0.5U	ug/l			
1,2,3-Trichlorobenzene	0.3J*	ug/l			
Hexachlorobutadiene	0.5U	ug/l			
Naphthalene	0.4J*	ug/l			
2-Chlorotoluene	0.5U	ug/l			
1,2-Dichlorobenzene	0.5U	ug/l			
1,2,4-Trimethylbenzene	0.5U	ug/l			
1,2-Dibromo-3-chloropr+	0.5U	ug/l			
1,2,3-Trichloropropane	0.5U	ug/l			
Tert-Butylbenzene	0.5U	ug/l			
Isopropylbenzene (Cume+	0.5U	ug/l			
p-Isopropyltoluene	0.5U	ug/l			
Ethylbenzene	0.5U	ug/l			
BENZENE, ETHENYL-(STYR+	0.5U	ug/l			
BENZENE, PROPYL-	0.5U	ug/l			
Butylbenzene	0.5U	ug/l			
4-Chlorotoluene	0.5U	ug/l			
1,4-Dichlorobenzene	0.5U	ug/l			
1,2-Dibromoethane (EDB)	0.5U	ug/l			
1,2-Dichloroethane	0.5U	ug/l			
4-Methyl-2-Pentanone	0.5U	ug/l			
1,3,5-Trimethylbenzene	0.5U	ug/l			

(Sample Complete)

19-JUL-91
41:

EPA Region X Lab Management System
Sa: 'Prc An is lts

Page 21

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A

Blank ID: PB 14.72

+-----+-----+-----+-----+				
Metals - Specified	Water-Total			
Blank #1	Result	Units		
+-----+-----+-----+-----+				
Arsenic	As-Total	1.5U	ug/l	
Chromium	Cr-Total	0.2J*	ug/l	

(Sample Complete)

11:41:40

Sample/Project Analysis Results

Project: HWD-127A RIDGEFIELD BRICK AND TILE

Officer: MLB

Account: AGDD3A


Blank ID: PB 16.97

Metals - Specified		Water-Filtere	
Blank #1		Result	Units
Arsenic	As-Diss	1.5U	ug/l
Chromium	Cr-Diss	2.0 *	ug/l

(Sample Complete)

APPENDIX G WELL CONSTRUCTION DIAGRAMS

Year	Number of Patients
1970	175
1980	185
1990	215
2000	235



SHEET NO.

PROJECT NO.